

19

of 'Tee Bar Stringer' transversal plank tee supports and their brackets renewed in forward and after wells.

Also approximately 20% of wooden plank renewed.

ENDORSEMENT OF CLASS :- Relating shell plate G. 4 & 5 (p.s. aft) indented
examined and found to continue efficient.

NOT DONE MACHINERY :- Propellers, after end of shaft bushes and outside fastenings, sea valves in machinery space examined and found or placed in order. =

N.B.—If this Report is copied by Copying Press, especial care must be taken that the copying paper is not so much damped as to spread the ink, or to cause it to show through to the other side.

SP. OL. PRA. 6. +100 A1

Glasgow (H) London 24/11/55.

BOOKING & COMPLETION OF SPECIAL SURVEY (Dr.)

NOV DOCK DOCKING :- Vessel placed in dry dock. Bottom, rudder, and stern frame cleaned, examined and recoated. The deck, casings, coamings, hatchways, ventilators, air and sounding pipes, steering gear, windlass and general equipment examined where practicable and found in satisfactory condition.

much of the work of the Special Survey :-

(1) Keel plate No. 6 (corroded) renewed. Also keel plates Nos. 7, 8, 9 & 10 pitted, cropped and partially renewed in way of strum boxes in centre tanks Nos. 2, 3, 4 & 5. The other keel plates examined and found to remain efficient.

408 v. Chen (between) allow refin one browser at viewing to find requ (c)

When Anchors or Cables are supplied, the particulars are to be reported in the following form:

ANCHORS.

Number of Certificate.	Anchors.*	WEIGHT EX. STOCK.			WEIGHT OF STOCK.			TEST PER CERTIFICATE.			WEIGHT REQUIRED BY RULE.			Description of Anchor.	Makers.	Where and when tested and Superintendent.
		Cwts.	qrs.	lbs.	Cwts.	qrs.	lbs.	Tons	Cwts.	qrs.	lbs.	Cwts.	qrs.			
	1st Bower															
	2nd "															
	3rd "															
	Collective Weight															
	Stream															
	Kedge															

* When a bower anchor is supplied to vessels, the weight of the stock should be entered in the column headed "Weight of Stock."

If licensed name of Patent

* When a bowler anchor is supplied it must be clearly stated whether it is a 1st, 2nd, or 3rd bowler.

CHAIN CABLES.

[illegible]

The vessel, so far as now seen, is in satisfactory condition and eligible for retention of class and fresh record of DOCKING 1/55., and Notation of S.S. Gen. 3/55 (Dr) as previously recommended.