


G.R. 130.

(LLOYD'S REGISTER.)**VESSELS OF 100 TONS AND UPWARDS.**

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping.

Signal Letters (if any)..... **V.C.K.D.**

Official Number.		Name of Ship.		No., Date, and Port of Registry.	
176005		EVANGELINE PARK		4 - 1945 Montreal, Que.	
No., Date, and Port of previous Registry (if any).				First Registry	
Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.	
British	Steam Screw	Pictou, N.S.	1945	Foundation Maritime Limited, Pictou, N.S.	
Number of Decks	One	Length from fore part of stem, to the aft side of the head of the stern post		Feet.	Tenths.
Number of Masts	Two			315	5
Rigged	Not	Main breadth to outside of plank		46	5
Stem	Raked	Depth in hold from tonnage deck to ceiling amidships ...		22	9
Stern	Cruiser	Depth in hold from upper deck to ceiling amidships, in the case of three decks and upwards		-	-
Build	In & Out	Depth from top of deck at side amidships to bottom of keel...		25	2
Framework and description of vessel	Steel Cargo	Round of beam		-	9
Number of Bulkheads ...	5 W.T.	Length of engine room, if any		44	0

Particulars of propelling Engines, etc. (if any), and Water Ballast Tanks, as supplied by Builders, Owners, or Engine Makers.

No. of sets of Engines	Description of Engines	Whether British or Foreign Made	When made	Name and address of makers	Reciprocating Engines		Rotary Engines	N.H.P. B.H.P. I.H.P. Estimated Speed of Ship
					No. and Diameter of Cylinders in each set	Length of Stroke		
One	Reciprocating Triple Expansion	Engines British	Engines 1944	Engines Canada Iron Foundries Ltd., Three Rivers, Que.	THREE 20"			N. H. P. 146
No. of Shafts One	Particulars of Boilers	Boilers British	Boilers 1944	Boilers Dominion Bridge Co. Ltd., Montreal, Que.	31"	39"		I. H. P. 1176
	Description... Scotch				55"			Speed
	Number Two							10-11
	Iron or Steel... Steel							knots.
	Loaded Pressure .. 200. #							

Number of water ballast tanks, and their capacity in tons:— **Six - 737 tons.**

008533-008540-0174

[P.T.O.]

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	2515.01	On account of space required for propelling power	926.33
Space or spaces between Decks		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from Goods or Stores of every kind not being the personal property of the Crew.	
Fore-castle Trunk	7.20	These spaces are the following, viz. :—	
Forecastle	9.25	Deckhouses 131.55	215.73
Bridge space	43.80	(Number of Seamen or Apprentices for whom accommodation is certified 43)	
Poop or Break	93.48	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows :—	
Side Houses	42.09	Cubic Meters.	
Deck Houses	118.94	Master's Accom. 10.22	
Chart House	4.77	Chart Room 4.77	
Spaces for Machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894		Passages 5.60	
Excess of Hatchways	60.24	Gyro Compass 4.32	95.13
		B'swain's Store 14.90	
Gross Tonnage	2894.78	Water Ballast 50.57	
Deductions, as per contra	1237.19	Total	1237.19
Register Tonnage	1657.59	W.T. Room 4.75	

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 376.99 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 89.82 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Galley 9.22, Wheelhouse 9.66, Steering Gear 18.78, Refrig. 9.24, Toilets 5.95,

Open Bridge 203.84, Open Forecastle 43.40, Light & Air 89.82 tons.

Name of Master	Certificate of { Service No. Competency No.
No. of Owners	
Name, Residence, and Description of Managing Owner if there are more owners than one.	
His Majesty the King, in right of Canada, represented by the Honourable the Minister of Munitions and Supply, of the Dominion of Canada, for the time being, Ottawa, Canada, Ontario.	
Sixty-four (64) Shares.	
Park Steamship Company Limited, of 410 St. Nicholas Street, Montreal, Que.	
Designated Managers.	
Dated Montreal, Que. January 22nd, 1945.	