

Port of LONDON.

12th June 19 47.

## REPORT ON MASTS, SPARS, AND RIGGING.

Dear Sirs,

Having, in accordance with your instructions,  
 examined the Masts, Spars, Iron Work of same, and Rigging, of the  
 (Name of Vessel) "L. KAGANOVITCH"

on the (Date of examination) 11th June 19 47,

I have to report that I found :-

Samson Post. Port stay to fit with thimbles and throat seizings.

Forestay & Stb. stays to renew. Rigging screws and shackles to  
 overhaul, and grease.

Funnels. Foreward funnel : Port and stb. forward stays to clean  
 and oil. Splices to reserv, shackles and rigging screws to overhaul  
 or renew. Port and starb. afterstays to renew. Rigging screws  
 to repair or renew, shackles and bolts to overhaul or renew.

After funnel : All stays to renew. Rigging screws, shackles and  
 bolts to repair or renew.

Mast. All spiderbands and ironwork on mast in good order.

/over

Fee £ : :

To the Surveyors,  
 Lloyd's Register of Shipping,



© 2020

Lloyd's Register  
 Foundation

Fore topmast stay to renew, rigging screw to supply and fit. Fore preventer stays to renew, rigging screws to overhaul.

Stb. after shroud to renew.

All other shrouds and stays to clean and oil.

Rigging screws, bolts and shackles to overhaul, repair or renew.

Lifts on top and lower yards in good condition.

All yard lifts fitted with insulators.

Lugs for bottomends of funnel stays may have to be repositioned to clear rails on deckhouses.

*John Bartor*  
*Foreman Shipwright*

*The above repairs have been effected.*

*E. L. Luce*



© 2020

Lloyd's Register  
Foundation

RAM  
"  
"  
IDE  
Fra  
"  
Rev  
Dep  
Fra  
"  
"  
"  
Diar  
Stat  
Are  
P  
an  
Are  
of  
th  
SINGL  
Floc  
Mid  
"  
"  
Side  
"  
"  
DOU