

Lloyd's Register of Shipping. *74d 3925*

-7 JUL 1941

Ship's Name "EMPIRE SUCCESS".

Official No. 167430.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

The freeboards of this vessel have been reassigned at this time.

The openings in the combined bridge & poop front have been permanently closed & suitably stiffened.

All overboard scuppers from the combined bridge & poop spaces have been permanently closed & the spaces drained to the bilges by scupper pipes.

The new freeboard markings have been verified & cut in on sides of the vessel.

Additional accommodation has been fitted at this time at the fore end of the bridge space (p.s.)

3 sidelights & 2 sidelights, all with deadlights of substantial construction have been fitted in shell & bridge front respectively.

W.C. with gate valve fitted. *with secondary means of control.*

Steel companionway fitted on bridge deck 5'-9" x 36" x 6'-6" high with strong hinged wood door 4'-6" with 21" coaming.

3 mushroom vents fitted to accommodation.

W. Robinson 6/41

SURVEYOR TO LLOYD'S REGISTER.

A copy of this information has been placed on board the vessel.

*W. Robinson 10/7/41**W. R.*