

"NORMAN"

This steel screw vessel was built at North Shields in December 1908 and classed 100A1 "Stm Trawler". The class however was withdrawn at the Owners' request in June 1927.

The GOTHENBURG Surveyors cable as follows:-  
"NORMAN OWNERS CONTEMPLATE SUBMIT VESSEL RECLASSIFICATION PLEASE FORWARD NEXT MAIL PARTICULARS FOR DRILLING".

In order to have the vessel's class reinstated in the Society's Register Book it will be necessary for the requirements of a 3rd S.S. No.3 to be complied with and all parts of the structure drill tested where deemed necessary by the Surveyors and full particulars of the equipment on board furnished together with any modifications that may have been effected to the vessel's structure since the class was withdrawn.

It is submitted the Gothenburg Surveyors be informed as above and that the original thicknesses of the shell plating which are in 20ths of an inch are as follows:-

A	9	to	8	at	ends
B	8	"	8	"	"
C	9	"	8	"	"
D	8	"	7	"	"
E (sheer)	10	"	8	"	"
RQD	10	"	8	"	"

*W. Bell*  
3.4.45.



© 2019

Lloyd's Register  
Foundation

068608-008617-0311