

1

GLASGOW.

DIS 668
TELEPHONE: CENTRAL 6491 (4 LINES).

Lloyd's Register of Shipping.

95, Bothwell Street, GLASGOW, C.2.

21st January, 1946.

S.

Dear Sir,

I was duly favoured with your letter of the 15th instant regarding Glasgow First Entry Report No. 70230 on the Motorship "EMPIRE GROSVENOR", and with regard thereto have to state that the Surveyor informs me that the general service pump of 20 tons/hr. capacity is connected to the cooling water system. Also there are two gear wheel pumps for lubricating oil driven direct by the main engine. One of the pumps forces the oil through a filter and an oil cooler to all principal bearings whilst the other pumps the oil from the collecting tank to the lubricating oil tank. If one of the pumps should get out of order it is possible to change over the lubricating oil system so that the pump which is still working pumps oil from the bedplate through filter and cooler to the bearings. No other lubricating oil pumps are fitted, and the Surveyor regrets that the above was not made clear on his report.

I am, Dear Sir,
Yours faithfully,

The Secretary,
LONDON.

Secretary to the
Glasgow Committee.

Foundation

008668 0205

Referred to the D.O.

Noted
L.F.
125/1/16 R.J.

24 JAN 1946

For Engineer Surveyors (F.E. Rpts.) to note.



© 2021

Lloyd's Register
Foundation