

s/s Dame
Hull Report No 23614 W.L.D. 3 MAY 1911

HULL.

12th April 1911.

F.C. Smith

the Builders Messrs Cook, Welton & Gemmell, Ltd, Beverley, visit the Steam Trawler "DAME", of Hull on the 8th April 1911 whilst on the St. Andrew's Slipway, Hull, for the purpose of ascertaining the nature and extent of the damage stated to have been caused in launching the vessel, February 2nd 1911.

FOUND	Recommended that
Damage starboard side.	
One shell plate B. Strake No. 6 from aft badly set up	One shell plate B6 from aft be renewed, faired and refitted.
One shell plate A Strake No. 6 from Aft badly set up.	One shell plate A Strake No. 6 from aft be removed, faired & refitted.
One keel plate adjoining A No. 6 badly set up.	One keel plate adjoining A No. 6 be removed, faired & refitted.
Three frames in way of above set in.	Three frames be faired in place
One floor badly buckled.	One floor be removed faired & refitted.

Also recommended that the coal be removed from the bunkers for further examination of the damage.

*211-0
1911-0*

© 2020
R. C. Smith
Lloyd's Register
Foundation
008728-008733-0171