

Lloyd's Register of Shipping.

Ship's Name S.S. "MOHAWK PARK"Official No. 175595

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in September, 1944.

ALTERATIONS - NOW DONE:-

No.5 'Tween Deck - Port Side - D.E.M.S. Accommodation removed and No.19 bulkhead extended to ship's side. One 18" dia. ventilator, one 12" dia. ventilator, three 6" dia. ventilators, nine portlights and two storm valves in way removed and openings closed with welded insert plates and doublers.

Starboard Side - One room removed necessitating removing bulkhead aft 4 frame spaces. One 2'-0" dia. escape hatch on upper deck and two portlights in way removed and openings closed with welded plates and doublers.

Forward Magazine in No.1 'tween deck removed together with access trunkway and hinged steel door. Deck aperture closed with insert plate, efficiently welded in place. Fore and aft girder extended and bracketed to collision bulkhead.

All new work satisfactorily hose tested on completion.

J. Caldwell

SURVEYOR TO LLOYD'S REGISTER OF SHIPPING

Vancouver, B. C.

18th December, 1945.

W. J. Caldwell
J. B. D.
14/2/46

