

CLASS CONTEMPLATED

## (LLOYD'S REGISTER.)

G.R. 130.  
Lloyd's Register.

## VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.  
Signal Letters (if any) L.D.J.F.

Official Number.		Name of Ship.		No., Date, and Port of Registry.	
161,241.		Surinam		' 85 in 1929 London.	
No., Date, and Port of Previous Registry (if any).					
Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.	
British	Steam Ship Twin Screw.	Belfast.	1929	Harland and Wolff Limited Belfast.	
Number of Decks	... One	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post		Feet.	Tenths.
Number of Masts	... One			325	0
Rigged	... Not	Length at quarter of depth from top of weather deck at side amidships to bottom of keel			
Stern	... Elliptical	Main breadth to outside of plank		55	2
Build	... Clencher	Depth in hold from tonnage deck to ceiling at midships		15	3
Galleries	... -----	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards			
Head	... -----	Depth from top of beam amidships to top of keel		17	0
Framework and description of vessel	Steel Cargo	Depth from top of deck at side amidships to bottom of keel		16	1.7
Number of Bulkheads	... Nine	Round of beam		1	0
Number of water ballast tanks, and their capacity in tons	Eight - 1982 tons.	Length of engine room, if any		54	0

## PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ... 5031 Tons. Ditto per inch immersion at same depth ... 37.7 Tons.

## PARTICULARS OF PROPELLING ENGINES, &amp;c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. B. H. P. I. H. P. Speed of Ship.
Two	Triple Expansion Direct Acting Vertical	British	1929	Harland and Wolff Limited Belfast.	Six 2-14½"	27"	----	228 1270 1400
No. of Shafts.	Particulars of Boilers.							
Two	Horizontal Cylindrical Return Tubes	British	1929		2-24"			
	Number ... Two				2-38½"			
	Iron or Steel ... Steel							
	Loaded Pressure ... 180 lbs.							10 knots

## PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ...	2228.69	On account of space required for propelling power	974.71
Space or spaces between Decks...		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	
Port or Trunk ...	492.90	These spaces are the following, viz.:—	
Forecastle ...		Poop and Round Houses	136.94
Bridge space ...		(Number of seamen or apprentices for whom accommodation is certified) 34	
Poop or Break ...	77.03		
Side Houses ...		Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Deck Houses ...	144.82		
Chart House ...			
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ...	102.52		
Excess of Hatchways ...			
Gross Tonnage ...	3045.96	Cubic Metres	
Deductions, as per Contra ...	1414.62	Masters Accommodation 6.58	
Register Tonnage ...	1631.34	Chart Wireless Space 4.57	
		Boatswains Stores 9.63	
		Ballast Pump Spaces 15.18	
		Water Ballast Spaces ...	302.97
		No. 3 Side Ballast Tank ...	1414.62
		P.S. 238.78	

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 300.34 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 153.13 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Space in Poop (Port)	L. 46.0'	-	44.19 tons
" " " "	L. 32.0'	-	28.65 -"
" " Aft of Fole	L. 4.0'	-	7.20 -"
Forecastle	L. 31.5'	-	59.77 -"

Name of Master	Certificate of { Service No. Competency No.
No. of Owners	
Name, Residence, and Description of Managing Owner (if there are more owners than one.)	
Lago Shipping Company Limited 21, Bury Street, London.	Hon. Andrew Alexander Morton Weir of 21 Bury Street, London, E.C.3. -Manager-
Shares:- Sixty-four.	
Dated 22nd May, 1929.	