

Recd from
14 Sept 7/11/56

21 AUG 1956

43998

Rpt. C. 11 (Contd.)

Index No.

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

Ship's Name T.S.S. "GUMHURYAT MISR" Official No. 137

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

(1) 29 port and 28 starboard sidescuttles Type 2 Ref: D BS
3024/47 now installed as follows:-

No. 1 Lower tween deck space	5 port 5 starboard
No. 1 Upper tween deck space	5 port 4 starboard
No. 2 Lower tween deck space	7 port 7 starboard
No. 2 Upper tween deck space	7 port 7 starboard
No. 4 Lower tween deck space	5 port 5 starboard

Vertical distance of lowest scuttle above base line is 22 feet.

(2) 1 port 1 starboard Gunmetal storm valve fitted in No. 2 lower tween deck for discharge from Pilgrim lavatories on upper deck.

(3) 5 ventilator coamings now installed on upper deck and upper tween decks in No. 1, 2 and 4 tween decks.

Size of openings in decks,

No. 1,	1'6" x 1'6".
No. 2,	2'6" x 1'0".
No. 4,	1'6" x 1'6".

Coamings minimum 3'0" high x 7/16 thick, coaming angles 3" x 3" x 3/8".
Doubling plates in way of openings, Nos. 1 and 2, 4'0" x 4'0" x 1/2"
No. 4, 3'6" x 2'3" x 1/2"

John W. ...

*Noted
JMB
11-12-56*



© 2021

Lloyd's Register Foundation

008759-008764-0234