

26 MAR 1954

Rpt. C. 11 (Contd.)

Index No. ....

# LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

Ship's Name "GUMHURYAT MISR" Official No. 137

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

New hatchways for access to No.4 Lower Hold have now been satisfactorily installed on Poop (C), Upper (D) and Main (E) decks.

	Poop (C) Deck.	Upper & Main deck.
Dimensions of hatchways.	17'-6" x 5'-1½"	16'-8½" x 5'-1½"
Coaming height above deck.	30"	9"
Thickness sides	1/2"	1/2"
ends.	1/2"	1/2"
Stiffeners horizontal	7" x 3½"	
Brackets centre	7" x 3½"	

Hatch covers, Material: pine with galvanised steel bands on ends.

Thickness: 2½"

How fitted: fore and aft.

Bearing surface: 2½"

Spacing of cleats: 6" from ends, 24" on sides 22" on ends.

No. of Tarpaulins: 3

2 small skylights on poop deck to previous accommodation below in way of new hatch, now cut away and dispensed with and deck openings plated over.

*Robert Sturges*

SURVEYOR TO LLOYD'S REGISTER OF SHIPPING

*Mr B. Chase*  
*noted*  
*45*

31 MAR 1954

