

Received 1 AUG 1953

Index No.

Govt. Copy

Owners C11

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

SURVEYS FOR FREEBOARD

(COMPUTATION FOR STEAMER, SAILING SHIP, TANKER)

Ship's Name INTAN	Official Number ✓	Nationality and Port of Registry INDONESIA DJAKARTA	Gross Tonnage 668.50 660	Date of Build 1953	Port of Survey GRONINGEN
Moulded Dimensions: Length 9.700 ✓ Breadth 2.958 ✓ m Freeboard Length 52.475 ✓ Moulded displacement at moulded draught = 85 per cent. of moulded depth 855 ✓ m ³ (excluding bossing) Coefficient of fineness for use with Tables .68 (ACTUAL .668)					Surveyor's Signature <i>[Signature]</i>
Particulars of Classification 100 A1 Contemplated					

DEPTH FOR FREEBOARD (D).

Moulded depth ... **2958** ✓
Stringer plate ... **7** ✓
Wood Sheathing on exposed deck
 $T \left(\frac{L-S}{L} \right) =$
see sketch
Depth for Freeboard (D) = **2965**

DEPTH CORRECTION.

(a) Where D is greater than Table depth
(D-Table depth) R = ✓
(b) Where D is less than Table depth (if allowed)
(Table depth-D) R = **8.33 (3.499 - 2.965) 13.252**
If restricted by superstructures **YES 56 m.**
SEE OVER.

ROUND OF BEAM CORRECTION.

Moulded Breadth (B) **9700** ✓
Standard Round of Beam = $\frac{B \times 100}{50} = 194$ ✓
Ship's Round of Beam = **195 NIL.**
Difference **+194**
Restricted to
Correction = $\frac{\text{Diff}}{4} \times \left(1 - \frac{S_1}{L} \right) = \frac{194 \times 0.038}{4} = +1.83$

DEDUCTION FOR SUPERSTRUCTURES.

	Mean Covered Length (S)	Equivalent Enclosed Length (S ₁)	Height	Height Correction	Effective Length (E)
Poop enclosed ...	12815	12815	2200	-	12815
" overhang ...	400	200	"	-	200
R.Q.D. enclosed ...					
" overhang ...					
Bridge enclosed ...	22550	22550	2200	-	22550
" overhang aft ...					
" overhang forward ...					
Forecastle enclosed ...	15460	15460	1250	1.25/1.83	10560
" overhang ...					
Trunk aft ...					
" forward ...		1/2 DIFF			
Tonnage opening aft ...	1250	725	2200		725
" " forward ...					
Total ...	52475	51750			46850

Standard Height of Superstructure **1.83 m**

" " R.Q.D. ✓

Deduction for complete superstructure **590 mm.**Percentage covered $\frac{S}{L} = 100$." " $\frac{S_1}{L} = 98.62$ " " $\frac{E}{L} = 89.28$ Percentage from Table, Line A & B **86.80**

(corrected for absence of forecastle (if required))

Percentage from Table, Line B. ✓

(corrected for absence of forecastle (if required))

Interpolation for bridge less than .2L (if required)

Deduction = **590 x .8680 = -512 mm.**

SHEER CORRECTION.

Station	Standard Ordinate	S	M	Product	Actual Ordinate	Effective Ordinate SEE OVER	S	M	Product
A.P. ...	691	1		691	593	1918	1		1918
1/4 L from A.P. ...	307	4		1228	222	854	4		3416
1/2 L " ...	77	2		154	61	211	2		422
Amidships ...	0	4		0	0	0	4		0
3/4 L from F.P. ...	154	2		308	165	165	2		330
3/4 L " ...	614	4		2456	635	635	4		2540
F.P. ...	1382	1		1382	1602	1602	1		1602
Total ...				6219					10228

Correction = $\frac{\text{Difference between sums of products}}{18} \left(.75 - \frac{S}{2L} \right) =$

If limited on account of midship superstructure.

Mean actual sheer aft =

Mean standard sheer aft =

Mean actual sheer forward =

Mean standard sheer forward =

Length of enclosed superstructure forward of amidships = **> .1L.**" " aft of " = **> .1L.**

If limited to maximum allowance of 1 1/2 ins. per 100 ft.

Deduction for Tropical Freeboard.

Addition for Winter and Winter North Atlantic Freeboard.

Depth to Freeboard Deck = **Ft.**
Summer freeboard = **Ft.**
Moulded draught (d) = **Ft.**
Keel allowance = **Ft.**
Extreme draught = **Ft.**
Deduction for Tropical freeboard and addition for = **Ft.**
Winter freeboard = $\frac{d}{4}$ inches = **Ft.**
Addition for Winter North Atlantic Freeboard (if required) = **Ft.**

Deduction for Fresh Water.

Displacement in salt water at summer load water line
 $\Delta = 1007 \text{ m}^3$
Displacement in fresh water at summer load water line
 $T = 3.91 \text{ m}^3/\text{cm}$
Deduction = $\frac{\Delta}{40 T}$ inches = **Ft.**

TABULAR FREEBOARD corrected for Flush Deck (if required)

Correction for coefficient **NIL**

Depth Correction ... **56**
Deduction for superstructures ... **512**
Sheer correction ... **56**
Round of Beam correction ... **1**
Correction for Thickness of Deck amidships ... **1**
Other corrections, scantlings, etc. ... **1**

+	-
	56
	512
	56
1	
1	624
	- 623
	Summer Freeboard = -151 mm.

SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, Wood, Steel, Deck :-

Tropical Fresh Water Line above Centre of Disc ... **6 cm**
Fresh Water Line " " ... **6 "**
Tropical Line " " ... **0.1 "**
Winter Line below " " ... **6.1 "**
Winter North Atlantic Line " " ... **11 "**

Tropical Fresh Water Freeboard **MINUS 1**
Fresh Water " **MINUS 1**
Tropical " **5 cm (LIMITED)**
Winter " **11 cm**
Winter North Atlantic " **16 cm**

INTAN

A new form should be prepared if any alterations that affect the freeboard have been made. If no such alterations have been made, the Surveyor should endorse the form on this side with his signature and the date.

Sheer @ Poop Front = 132 mm. Excess Tw. Sk. Mt. = 370 Total = 502.

$$\text{Virtual Sheer @ A.P.} = 502 \times \frac{26.238^2}{13.423^2}$$

$$= 1918$$

$$\text{Actual Sheer @ A.P.} = 593$$

$$\text{Excess Tw. Sk. Mt.} = 370$$

$$\text{Mt. of Poop} = 1824$$

$$2287$$

Use 1918.

Depth Correction.

$$\text{Correction Factor} = 26.5195 + \frac{1250}{1830} \times 4.9655$$

$$31.485$$

$$= \frac{26.5195 + 3.392}{31.485} = \frac{29.9115}{31.485} = .9503.$$

$$\text{Actual Depth Correction} = 59 \times .9503$$

$$= 56 \text{ mm.}$$

Trade of ship

INTERNATIONAL

Names of sister ships

"BARLIAN", "BIDURI", "PERMATA", "MUTIARA", "PUSPARAGAM" (except minor items on deck)

Builder's name and yard number

N.V. Ferus Smit 7/1 J. Smit & Zn, Foxhol, yard no 116

Owners

Republik Indonesia

Fee

f 190.-

List of plans forwarded for reference. (See "Instructions to Surveyors, Part 4, 1950," paragraph 11.)



© 2021

Lloyd's Register
Foundation