

on the ~~Wood, Iron or~~ Steel. S. S. Freshener

NET 98.92

Managers.

..Port belonging to...London

Cell D Bor D Ba feet ; uE & B feet ; f feet

total capacity 1 tons. FPT 1 tons; APT 1 tons; MT 1 feet 1 tons.

N.B.—All alterations in the existing records should be underlined.

Last Report, No. 21155 Port AFBN

Particulars of Classification *(which must be inserted precisely as in Register Book & Supplements)*

CHARACTER. * For Special Survey. Date of last Survey and of Periodical Surveys.	Machinery and Boiler Surveys (Including date of N.B., if any).
+ 100A1 7-42	+ L.M.C. 7-42 O.G.
For Admiralty Tender Service.	

In damage cases where the Surveyor has not made a special damage report he is required to state whether he offered his services for this purpose and to whom and why they were declined. ✓

Society's Freeboard (if assigned) as } ft. ins
painted on Ship and now verified }

Was a damage report made by anyone else? if so, by whom? ☒

REPAIRS, OR EXAMINATION AS PER RULE, FOR Condition & Docking & Damages

Now Done The vessel placed on the Trolley Bottom, keel & rudder cleaned & examined & recoated. The decks, Fresh water tanks, machinery spaces, casings, vents, steering gear, windlasses, & general equipment examined & found in good condition Annual Freeboard Survey held See Abn. Rpt. 21150.

Propeller, aft end of Stem bush & all outside fastenings examined & found in good condition.

The following indented plating has been noted. Port house pipe broken at top of flange.

Stem bar set over to Starb. at E strake No's 1 & 2 keel plates set up. S.A. 1 & 3 plates indented S.B. 1 & 3 S.C. 1 & 2 S.D. 1 & 2 3 & 4 5 & 6 S.E. 1 & S.F. 1 P.A. 3 P.B. 1 & 3 P.C. 3 & 4 P.D. 1 & 2 3 & 4 5 & 6 P.E. 1 & 2 P.F. 1 & 2

Temporary Repair Now Done: All started rivets & landings hardened up, & hose tested on completion of repair & found tight Port house pipe broken flange repaired by Electric Welding

Note: Particulars of this vessel have been taken from Classification Certificates on board.

SUMMARY OF DAMAGE REPAIRS :—	Shell Plates.	Frames.	R. Frames.	Floors and Bracket Floors	Beams.	Inner Bottom Plates.	Dk. Plates.	Other Items :—
Renewed								
Removed and Fair'd or Repaired								
Fair'd or Repaired in place ...								

PRESENT CONDITION OF THE							
Decks	Good	Bulkheads	Good	Engine Room Skylights	Good	Copper, or Y.M.	✓
Caulking of Decks	"	Celling	✓	Coal Bunkers, Openings, Covers, &c.	✓	(State if on Felt.)	
Coamings	"	Cement or Asphalt	✓	Oil Bunkers	✓	When fitted, Month	✓ Year ✓
Beams & Fastenings	"	Rudder	Good	Scuppers	Good	Boats	Good
Outside Plating	"	Steering gear and its connections	✓	Cargo Hatchways	"	Masts, Yards, &c.	"
" " in way of sidelights	✓	Windlass	"	Hatches	✓	Condition, how ascertained	See deck
Frames	As repl. Good	Have pumps been examined and found efficient?	✓			(State if wedges removed.)	No.
Reverse Frames	"	Have Sluice Valves been examined and found efficient?	✓	Planking		Equipment letter	✓
Longitudinals	"	Have Watertight Doors been examined and found efficient?	✓	Caulking		Anchors, No. of	2
Transverses	✓	Have Ventilators and their Coamings been examined and found efficient?	4/2	Treenails		Cables (State if now ranged)	No. Stated in
Floors	Good	Air and Sounding Pipes	"	Breasthooks & Stemson		" length	order mean diamr. ✓
Keelsons	"	Doubling Plates under Sounding Pipes	"	Transoms, Pointers & Crutches		(on board.)	
Stringers	"			Timbers of Frame at openings		" Rule length	✓ size ✓
Inner Bottom Plating	✓			" " at other places		Chain Locker	✓
Have the Tanks been examined internally?	4/2			Stringers, Clamps & Shelves		Hawsers & Warps	Good
Have the Tanks been tested?	No			Sailing		Standing and Running Rigging	"
				(State if examined.)		Sails	✓

General Observations, Opinion as to Class, Recommendation, &c.:—

State clearly whether any and, if so, what alteration is suggested to be made in the existing classification and notification of the vessel in the Register Book consequent upon this survey, thus, for example:— "to remain as classed in the Register Book *without fresh record of Survey*," "to remain as classed and to have record of survey, 138" or "to remain as classed and to have record of survey, 138, and the notations of *ss No. 138*."

This report is forwarded for the information of the Committee.

Key Fee (per Section 29)	£	:	:	Fees applied for
Special Damage or Repair Fee (if any) (per Sec. 29)	£	3	3	0. 5-8 1944
Travelling Expenses (if chargeable)	£	:	:	Received by me
Second Surveyor's Fee (if any)	£	:	:	19

Committee's Minute.....

Character Assigned..... 843 Abu Subject *[Signature]*

(note to Helen

0088/2-008822 - 0099

E. Eamshaw
 Surveyor to Lloyd's Register of Shipping

Lloyd's Register
Foundation

Is Certificate required? If so, to be sent to