

Received by Chief Ship Surveyor

Received from Chief Ship Surveyor

HB

VESSEL'S NAME

"K I L I N S K I"

REPORT

Gdy.

Nos. 3126

(2108 Suppl.)

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

This vessel holds the provisional class 100A1 (Classification Contemplated) with Notation of 'Examined 7.48' valid for 12 months.

The class is subject to watertight entrance door to the tunnel as required by the Rules being fitted at the first opportunity.

The greater part of the Special Survey for Classification was held Gdy. 7.48.

The GDYNIA Surveyors report (8.49), the vessel placed in dry dock and the Special Survey for Classification advanced by the internal examination and testing of Nos. 4 D.B. tanks (p & s) and cofferdams in way.

TO COMPLETE S.S. FOR CLASSIFICATION :-

No.4. centre D.B. tank requires to be internally examined.

Two keel plates and five bottom plates (p & s) found indented and it is recommended these be specially examined at the next drydocking, bottom plating found wavy amidships.

The Surveyors recommend this item be recorded as an endorsement of class.

A tunnel W.T. door in accordance with the Rules has now been fitted.

IT IS SUBMITTED the vessel is eligible to have record of docking survey 8.49.

IT IS FURTHER SUBMITTED ACTION be DEFERRED for completion of Special Survey for Classification.

8.49 Gdy.

INSERT/IN S.R.L.

Keel plates Nos. 3 & 4 forward and bottom plating in way (p & s) to be specially examined at next drydocking.

DELETE/ FROM S.R.L.

Tunnel W.T. door to be fitted



© 2020

Lloyd's Register
Foundation

P.T.O.

-2-

"K I L I N S K I"

ENDORSEMENT OF CLASS (B).

Bottom plating amidships wavy.

Jmb
4.10.49

LM

CSS. Records Dept.

to note.

Wavy bottom.

CLASS. SURVEY PART HELD.