

SCALE  $\frac{1}{2}$  INCH = ONE FOOT

NEW BULKHEADS: PLATES 3/8" THICK VERTICAL STIFFENERS 5"x8"x40  
SPACED 30" APART WELDED TOP & BOTTOM.  
BULKHEAD FRAME 3"x3"x36" SINGLE. DECK  
ANGLE 3"x3"x30" SINGLE. SEAMS OF PLATING SINGLE  
WELDED NO BULKHEAD LINERS.



Dredger "India" don. rept.

No. 93084

Midship Section (relaying the wing.)



© 2020

Lloyd's Register  
Foundation

009008-009014-0069