

SCALE $\frac{1}{2}'' = 1 \text{ FOOT}$

CLASS 100 A.1. AT LLOYD'S. CARRYING PETROLEUM IN BULK

$LENGTH = 442' 6'' \text{ B.P.}$
 $BREADTH = 60' 0'' \text{ MLD}$
 $DEPTH = 32' 0'' \text{ MLD}$
 $L \times D = 14160$
 $L \times (B+D) = 40710$
 $\frac{L}{D} = 13.83$
 $d = 28.46$

EQUIPMENT:-
3 BOWER ANCHORS COLLECTIVE WEIGHT 207 CWTs (STOCKLESS) 69 CWTs EACH
1 STREAM ANCHOR 200 CWTs (EX-STOCK)
300 FATHOMS $2\frac{1}{4}$ TAYCO CHAIN CABLE
120 FATHOMS 5" CIRC. STEEL WIRE (STREAM) (6" x 2")
120 FATHOMS 5" CIRC. STEEL WIRE (TO WIND) (6" x 2")
2 AT 100 FATHOMS $2\frac{1}{4}$ CIRC. STEEL WIRE (CHAINSEARS)
2 AT 100 FATHOMS $2\frac{1}{4}$ CIRC. STEEL WIRE (WARS)

EQUIPMENT NUMERALS

L * (B + D)	=	40710
POOP	=	94' 0"
BRIDGE	=	45' 0"
FORECASTLE	=	35' 0"
	174	x 7.5 * 3/4 = 978
MIDSHIP HOUSES	=	27' 0"
CASING	=	51' 0"
	88	x 7.5 * 1/2 = 330
		42018



Blythwood S. B. Co.

No 37 San Amado

Mids hip Section

(As built)

GLASGOW REPORT No. 55339



© 2020

Lloyd's Register
Foundation

002015 - 002020 - 0002

Lloyd's



© 2020

Lloyd's Register
Foundation