

25.5.16  
12.12.16 (108)  
15.4.18 (110)

Coupling 14" diam. x 2 3/4" thick  
Keyed and Bolted  
6 - 1 3/8" bolts with nuts and pins.

NOTE: If any scantling strengthening etc. which we have herein  
submitted, be in excess of your minimum requirements  
kindly amend same.



Rudder Stock 5 3/4" at head to 4 1/2" at heel, Swelled 10" diameter in way of arms  
Loose Pinholes 3" Diameter  
Rivet holes reeled 1 3/16" diam. spaced 5 1/16" or 6" c/c

Arms 34" x 3 3/8" to 34" x 1", spaced 48" apart, centre to centre.

# SINGLE PLATE RUDDER

S/S N<sup>o</sup> 106 109 110

Scale 1/2 inch = 1 Foot.



Lloyd's Register  
Foundation

009021-009029-00906

Campbelltown S.S. Co. Ltd.  
No 109 & 110 ~~###~~

Rudder Plan

Transferred to plan Kechn  
dis 475

S. S. "WAR ROTHER" N: 109.

S. S. "DRYBURGH." \* N: 110.

Gr. Report N: 17423  
& N: 17499.



W.  
~~IB~~ 177 See 2



© 2021

Lloyd's Register  
Foundation

0091021-0091029-00910