

# (LLOYDS REGISTER.)

G. R. 130  
Lloyds Register.

## VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyds Register of British and Foreign Shipping.

Signal Letters (if any) *T.V.T.P.*

Official Number.	Name of Ship.	No., Date, and Port of Registry.
142,742	War Cowslip	447 in 1918. London.

No., Date, and Port of Previous Registry (if any). ✓

Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Ship, screw	Govan, N.B.	1918	Harland & Wolff, Ltd., Govan, N.B.

Number of Decks ...	One	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ...	Feet.	Tenths.
Number of Masts ...	One			
Rigged ...	Sloop	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...	400	9
Stern ...	Elliptical			
Build ...	Clincher	Main breadth to outside of plank ...	399	5
Galleries ...	None	Depth in hold from tonnage deck to ceiling at midships ...	52	3
Head ...	None	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ...	28	5
Framework and description of vessel ...	Steel, cargo vessel	Depth from top of beam amidships to top of keel ...	-	-
Number of Bulkheads ...	Seven	Depth from top of deck at side amidships to bottom of keel ...	32	0.8
Number of water ballast tanks, and their capacity in tons ...	Seven 1404 tons	Round of beam ...	31	1
		Length of engine room, if any ...	1	1
			47	7

### PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ... 10570 Tons. Ditto per inch immersion at same depth ... 41.5 Tons.

### PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. I. H. P. Speed of Ship.
One	Triple expansion inverted	British	1918	Harland & Wolff Ltd, Belfast.	Three 27"	48"	-	518
No. of Shafts.	Particulars of Boilers.	Boilers.	Boilers.	Boilers.				
One	Cylindrical Iron or Steel Loaded Pressure 182 lbs	British	1918	Denny Bros Ltd, Dumbarton.	44"	73"	-	3000 11 1/2 knots

### PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ...	4816.58	On account of space required for propelling power	169.3.36
Space or spaces between Decks...		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	
Turret or Trunk ...		These spaces are the following, viz.:-	
Forecastle ...		Officers in Deck houses	
Bridge space ...		Crew in Poop.	232.11
Poop or Break ...	162.75	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:-	
Side Houses ...	39.65	Cubic Metres	
Deck Houses ...	116.75	Wireless Room 4.25	
Chart House ...	7.79	Master's Accommodation 7.88	
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ...	62.93	Boatwain's Stores 25.39	
Excess of Hatchways ...	85.29	Chart space 7.49	
Gross Tonnage ...	5291.74	Water ballast spaces 99.59	
Deductions, as per Contra ...	2070.17	Total ...	2070.17
Registered Tonnage ...	3221.57		

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 638.61 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 109.45 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Forecastle 37.6 ft long = 74.10 tons  
less hatchways & side houses = 6.43 " } 72.67 tons  
Bridge length 112.6 ft = 453.18  
less hatchways, part coal shoot & roundhouse = 99.26 } 353.92 tons

Name of Master

Certificate of { Service No. Competency No.

No. of Owners

Name, Residence, and Description of Managing Owner if there are more owners than one.

His Majesty represented by the  
Shipping Controller, London.  
Sixty four Shares.

Managers.  
Joseph Temperley & Co.  
87, Bishopsgate  
London, E.C.2.

Dated 12th December, 1918.