

COPY

LLOYD'S REGISTER OF SHIPPING

MEIKAI BUILDING

No. 32, AKASHI MACHI,

GRAMS: "REGISTER" KOBE

PHONE: 2530 SANNOMIYA

KOBE, 10th November, 1926.

Messrs. Nisshin Kaiun,

KOBE.

S.S. "TOKU MARU".
Completion of
Special Survey 2nd No. 3.

Dear Sirs,

In connection with the above vessel, I have to inform you that the following requires to be done to complete the S.S. 2nd No. 3, viz:

- (1) Shell plating and framing throughout the holds and bunkers to be scaled, examined and recoated.
- (2) Shell plating to be drilled and thicknesses gauged.
- (3) Spar deck plating " " " " " " .
- (4) Under Donkey Boiler, centre girder and floors to be placed in good condition.
- (5) Under forward end of Condenser, 3 floors - upper half to be doubled or part renewed.
- (6) Under thrust recess on port side, 2 side girder intercostals - upper half to be renewed.
- (7) 45 fathoms of chain cables to be renewed at first convenient opportunity.

© 2020
I am, dear Sirs,

Yours faithfully,

Lloyd's Register
Foundation
a Watt
SURVEYOR TO LLOYD'S REGISTER.