



PARTICULARS FOR FREEBOARD

TONNAGE COEFFICIENT ABOUT	.78
LENGTH OF FORECASTLE	39.50
" " BRIDGE (ALL ENCLOSED)	103.50
" " POOP FOR 2 OF A.P.	26.75
LOWEST POINT OF SHEER	AMIDSHIPS
SHEER AT STEM AT UPPER DECK	6'-9"
" " 1/8 L. FROM STEM	3'-9"
" " 1/4 L. " " "	1'-8 1/2"
" " 3/8 L. " " "	0'-8"
" " STERNPOST AT U.D.	2'-10 1/2"
" " 1/8 L. FROM STERNPOST	1'-5 1/2"
" " 1/4 L. " " "	0'-8"
" " 3/8 L. " " "	0'-2 1/2"

TO CLASS 100 A.I. AT LLOYD'S

DIMENSIONS

LENGTH B.P.	370'-0"
BREADTH MLD	53'-0"
DEPTH MLD TO UPPER DECK	30'-0"
DEPTH "d"	17'-0"
L/D TO UPPER DECK	12.5
L/D TO BRIDGE DECK	9.8

TRANSVERSE N° = {53+30} = 83

LONGITUDINAL N° = {83+370} = 36710

EQUIPMENT N° = 31970

EQUIPMENT LETTER "X"

BOILER	ANCHORS	STOCKLESS	50% C.WTS. EACH
1	"	"	47 1/2"
1	STREAM	"	18 3/4"
1	KEDGE	"	8 3/8"
270	FMS	2 1/8"	STUD CHAIN CABLE
90	"	4 1/2"	S.W.R. STREAM
120	"	4 1/2"	S.W.R. TOWLINE
4	MANILLA HAWSERS	7"	EACH 90 FMS.

HULLS N° 212-13

TYPE SECTIONS 11

FREIGHTER FOR A.C.W.

79390

APPROVED

W. S. SUTHERLAND





© 2021

Lloyd's Register  
Foundation

009067-009073-0107