

Steel Screw Cargo Steamer, Number not given, proposed to be built by Messrs. Cammell Laird & Co. Ltd., with a view to class 100A1 "With freeboard".

Rule Dimensions : 205 x 33 x 16 feet to upper deck
24 feet to bridge deck

Scantling Numbers (Equivalent depth) 2732 and 9497

Proportions : Length = 12.81 to upper deck
8.54 to bridge deck.

Plans of midship section and outline general arrangement have been forwarded by the Builders direct, with a request that the scantlings may be examined and the minimum requirements, which could be recommended to the Committee for approval, indicated thereon.

This proposal is the same as that dealt with on the 28th ultimo for Messrs. Sir W.G. Armstrong, Whitworth & Co. Ltd.

The ship is a single deck cargo steamer, with a fore-castle and long bridge, and is intended for the Isle of Man Steam Packet Coy.

The arrangements submitted by Messrs. Cammell Laird & Co. are generally similar to those proposed to be adopted in the previous case referred to, but, in this case, the draught desired is 12' instead of 11'-6" to the bottom of the bar keel.

This draught is about 2'-9" less than the draught corresponding to the freeboard which could be assigned to a full scantling ship with the sheer and ~~scantlings~~ ^{erecting} as proposed.

As requested by the Builders, the scantlings have been amended to show the minimum requirements which could be recommended to the Committee for approval for the class 100A1 with a freeboard corresponding to the draught proposed, and it is submitted the plans be returned to the Builders for their information and guidance.

If the construction of the vessel is proceeded with, the usual detailed classification plans should be ^{submitted} ~~forwarded~~ for the ^{approval} ~~information~~ of the Committee.

As in the previous case, it is observed that provision is intended to be made for the steamer to lie aground, and the Builders' attention should be directed to the Committee's recommendations regarding such vessels as contained in Section 8 clause 5, and Section 10 clause 14 of the Rules.

Rgr

1.1.29

Wd.



© 2021

Lloyd's Register
Foundation

009083 - 009093 - 0084 2/2