

Lloyd's Register of Shipping.

(Report on Vessel No. _____ Port _____)

No. 346. SHIP ~~FORGINGS~~ OR CASTINGS.

I have to report that the undermentioned ~~Iron or Steel Forgings or Castings~~, manufactured by The Mitsubishi Zosen Kaisha, Ltd., of Nagasaki Works, for the Vessel No. 347, being built by them, of _____ have been inspected by me as set forth below and found to be, so far as can be seen, sound and free from defects.

THE WORDS FORGINGS OR CASTINGS, IRON OR STEEL, SHOULD BE STRUCK OUT AS MAY BE REQUIRED.

Mark on Forgings or Castings.

Lloyd's

No. 346.

29.3.21.W.B.

NAGASAKI. 1st April, 1921.

M. Boyle

~~Shaft Brackets.~~
~~STERN FRAME.~~

RUDDER FRAME.

STEM.

Material* ...	Cast Steel		
How made ...	Open Hearth		
Dimensions ...	As per Plan.		
Progress on Inspection ...	Finished.		
Date when Inspected	22-1-21 to 29-3-21.		
CASTINGS.			
Tests on Standard Test Pieces.			
Tensile Test—	29.4 & 28.8 tons		
Tons per square inch	27.1 & 22.9		
Extension per cent. ...			
Cold Bending Test—	126° & 131°		
Angle before fracture			
Drop Test—	10 ft		
Height from ground ...			
Hammering Test—	Yes		
If made according to Rules and found satisfactory ...			

SKETCHES OF FRAMES SHOWING POSITION AND DESCRIPTION OF WELDS OF FORGINGS.

Fee (if any chargeable) £

To be paid at



© 2021

Lloyd's Register Foundation

* If of Iron, state whether scrap or puddled Iron. If of steel, state whether made on the Open Hearth process.