

Empire Consequence

odho - Capus Boiler

W.P. 235 ~~10~~ 10".

es 2" o/o.

ventures not exposed to the flame the Society's
ness require thickness .1327"

Proposed to fit tubes .134" thick for the
pieces of the Combustion chambers and
the products of combustion first pass through
corrugated furnaces it is considered that
tubes could be regarded as being away
the flame and the proposed thickness of
" could be accepted.

the owners accordingly noted Ref.

10.9.46.