

s.s. "INDUS 6" ex "SKUDD IV"


Rule Dimensions:- 112.75' x 23' x 14' to Upper Deck.

Scantling Nos:- 1579 and 4172.

Proportions:- L = 8.05 depths to Upper Deck.

Owners:- Cia. Industrial de Valparaiso.



29 See Norske Veritas Reg. Book

This vessel was built in 1930 by Nylands Vaerksted, Oslo, and classed  1A1 "Whaler" with the Norske Veritas.

The Owners desire to have the vessel classed with this Society, and the Valparaiso Surveyor has forwarded plans of Midship Section and Profile and Deck, together with a First Entry Report. These have now been examined and the scantlings and arrangements found to be in accordance with or equivalent to the Society's requirements for the Class of A-"Whaler".

It is observed that considerable difference exists between the equipment indicated on the Midship Section and that shown on the First Entry Report. It is concluded that the First Entry Report indicates the vessel's present equipment, which, however, is not such as would entitle the vessel to the figure '1' until the Surveyor has satisfied himself, by examination of the appropriate certificates, that the anchors and chain cables have been properly tested, and until a kedge anchor of $2\frac{1}{2}$ cwts. weight ex stock, tested in accordance with the Society's Rules is placed on board.

It is submitted the Reports Department be advised accordingly.


21st March, 1947.




© 2021

Lloyd's Register
Foundation

009152-009160-0021