

Lloyd's Register of Shipping,

LOYD'S REGISTER,
LONDON.

42c, Sagarimatsu,

EC2 24 NOV 1919

Nagasaki, 18th October, 1919.

Reference

AN82

Dear Sir,

I am in receipt of your letter of the 5th Sept, 1919.
regarding Report of Survey of s. s. " Genoa - Maru " and wish
to state that the frames in the ^{engine} and boiler space are channels
10"x 3½"x.50" thick at web and .51" thick at flanges, and in the
holds are channels 10"x3½"x 7/16" thick at web and .47" thick at
flanges as shown on the profile.

Regarding the shelter deck beams I also wish to state
that these bulb angle section were manufactured by the Cambria
Steel Co. U. S. A. and were approved by Kobe Office as being the
nearest equivalent section to the British Standard Section.
Approved list of substitutions is herewith enclosed.

The bottom was cemented as required & found satisfactory.

I am, Dear Sir,

Yours faithfully,

R. Crawford.

The Secretary,

London.



© 2021

Lloyd's Register
Foundation

009161-009169-0048

009161-009169-0048

