

DISCLASSED SECRET

Lloyd's Register of Shipping.

SURVEYS FOR FREEBOARD.—STEAM SHIPS.

Index No. 16281
(For London Office only.)

PARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH TOP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey NO 13. 1. 33
Date of Survey
Name of Surveyor

Ship's Name.	Port of Registry and Nationality.	Official Number.	Gross Tonnage.	Date of Build.	Particulars of Classification
CUBAN GO	Lisbon Portuguese		5820	1903	+ 100 71 298

Registered dimensions from Ship's Register.	LENGTH.	BREADTH.	DEPTH.	UNDER DECK TONNAGE.	
	425.00	53.00	29.45	5353	
Length on LOADLINE.	425.00	Frame Depth 6 Rule " 6	Ceiling Sheer + .33	Peak 7 Tanks + 37	
CORRECTED DIMENSIONS.	425.00	53.00	29.78	5390	

Co-efficient of fineness.....	80.3
Any modification necessary [Para. 4 (a) to (e)]*	C. D. B
Co-efficient as corrected	78.
Sheer { Stem 96 at Sternpost ... 33 } 129 ÷ 2 = 64.5... Mean	
Sheer at $\frac{1}{2}$ of the length from { Stem 52.75 Sternpost 18.25 } 71.00 ÷ 2 = 35.5... Mean	
Gradual mean Sheer 64.54	+ .53 = 64.54
Standard mean Sheer [Table, Para. 18] 52.50	Correction
Difference 12	÷ 4 =
§ If limited as Para. 18 (f)	- 3

Rise in Sheer { At front of bridge house..... from amidships [Para. 18 (e)] { At after end of forecastle	✓
Fall in Sheer { Para. 18 (d) { ✓	÷ 2 = ✓
Length uncovered	/ Correction ✓

ALLOWANCE FOR DECK ERECTIONS :—			
Freeboard, Table C.....	5' - 3 $\frac{3}{4}$ "		
Correction for Length, if required (Para. 12, 13, and 14)	+ 3		
	5' - 6 $\frac{3}{4}$ "		
Freeboard by Table A. corrected for sheer, and for length, if required (Para. 11, 12, 13, and 14)	8' - 9 $\frac{1}{2}$ "		
Difference	3 - 2 $\frac{3}{4}$ "		
Percentage as below.....	29.90		
	11 $\frac{1}{2}$ "		

Correction for R. Q. Dk. if engine and boiler openings not covered by bridge house (Para. 11)	✓
Allowance for Deck Erections	0' - 11 $\frac{1}{2}$ "
Length.	Length allowed.
Forecastle..... 50.00	50.00
Bridge House 122.33	91.75
† Raised Qr. Dk.....	
Poop..... 58.00	58.00
Total	199.75
Length of Ship	425 = .47
Corresponding percentage (Para. 11, 12, 13, or 14) {	29.9.

SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, Wood , Steel, Deck :—		
Tropical Fresh Water Line above Centre of Disc ...	3077	Tropical Fresh Water Freeboard ...
Fresh Water Line " " " ...	161	Fresh Water " " " ...
Tropical Line " " " ...	146	Tropical " " " ...
Winter Line below " " " ...	146	Winter " " " ...
Winter North Atlantic Line " " " ...	v	Winter North Atlantic " " " ...

FW = $\frac{25.12}{4}$ 161 m/m MARKING FORM 14 NOV 1933 MARKING FORM 6 JUN 1934 MARKING FORM 11 FEB 1933

RECEIVED RECEIVED RECEIVED