

## LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

10 FEB 1959

## ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name "FLYING FALCON" Official No. 164034

Port of Registry GLASGOW.

This ship has been under survey at IRVINE

on JANUARY 1959 and the following alterations to the <sup>ORIGINAL</sup> conditions of

assignment of loadlines have now been effected/found:— as per instructions obtained from Head office as per S.R.L. Appendix.

ON FREEBOARD DECKMANHOLE TO AFT PEAK

On Freeboard Deck Aft, coaming 22" diam x 18" high x 3/8" thk, W.T. cover plate, 5/16" thk, secured by 8 - 1/2" bolts, welded to flange of coaming, rubber packing fitted.

SKYLIGHTS - 2 OFF

One on Freeboard Deck at front of deckhouse.  
One on Freeboard Deck at aft end of E.R. casing.  
Both skylights strongly constructed of steel with hinged W.T. covers, 1 - 10" dia fixed bullseye light on each cover, cover secured by 2 toggles with rubber packing, height to sill above deck 21". 1 - 10" dia fixed bullseye on top of skylight clear of cover.

G. B. Taylor  
Lloyd's Register, Glasgow,  
4/2/59

checked  
H. 7.11.2.59

A copy of this Report has been placed on board.

