

— N^o. 156. (YARD N^o). —

MIDSHIP SECTION.

— 135'-0" x 23'-6" EX x 13'-4" MLD. —

— SCALE $\frac{1}{2}$ " = 1 FOOT. —

— CLASS 100 A1. (FISHING PURPOSES). —

— STEEL. —

MLD BREADTH = 23'-4 $\frac{1}{2}$ ".

23.37
13.33
36.70 = 1ST NO.
135 = L
4954.5 = 2ND NO.

$\frac{L}{D} = 10.1$
 $\lambda = 12.00.$

BULWARKS 3'-11" HIGH ON MAIN D^K.
— " — 2'-11" — R^D Q^R D^K

6" x 3/20" B.P.
SPACED 6'-0"

5/16" SEE PROFILE & DECK PLAN
3" x 2 1/2" x 5/20"

RAISED Q^R D^K AS PER PROFILE

5" x 3" RP

7" x 9/16"

DECK PLATES 5/16"

28" x 3/8" TO 19" x 5/16"

OAK WATERWAY 14" WIDE.
DOUBLE LUGS.

3" x 3" x 3/8"

10/16" TO 8/16"

UPPER SIDE STR.
5" x 4" x 8/20"

BEAMS. 6" x 3" x 9/20" ON ALT. FRAMES. CAMBER 7"

FRAMES. 4" x 3" x 9/20" SPACED AS PER PROFILE. 4 3/4 RIVETS.

REV. - DO. 3" x 3" x 3/8" ACROSS FLOORS ONLY. NO REV. BAR.
WHERE SOLID CONCRETE IS FITTED.
LARGE SINGLE REV. BAR IN E & B SPACE 3 1/2" x 3 1/2" x 19/20".

FLOORS. 16" x 6/16" FOR 3/5 L. TO 5/16" BOILER BEARERS 5/8"

ENGINE FLOORS 8/16". OTHER FLOORS IN E & B = 7/16"

BHDS. FRAMES 4" x 4" x 4". PLATES .28" STIFFS AS PER RULE.

STERN FRAME & RUDDER. (AS PER PLAN).

PILLARS 2 1/2" DIA.

EQUIPMENT.

POWER 8" SLESS
7 1/4"
3 1/4"
120 FTMS 1 1/8" STUD LINK
60 FMS 6" HAWSER.
60 " 5" WARP

5" x 4" x 8/20"
LUG 5" x 3" x 5/20"

7/16" TO 6/16"

2 PP

D.R.

7/16" TO 6/16"

6" x 4" x 1/2" } 45'-0" X
9" x 1/2" B.P.

RISE OF FLOOR.
2'-6"

CR. K'SON 10" OF
12" x 3 1/2" x 3 1/2" x 20" CHANNEL.

LUG 3" x 2 1/2" x 6/20"

5" x 4" x 8/20"
LUG 5" x 3" x 5/20"

16" x 6/16"

D.R.

6/16" TO 5/16"


STEM & KEEL 8" x 2"
SCARPHS 13" LONG

NO BACK BARS TO BE FITTED.

RIVETING.

RIVETS IN KEEL & STEM & STERN POST 1" DIA.
GARB & SHEER STRAKE BUTTS STRAPPED & D.R. 3/4 DIA.
REMD^R OF SHELL & STR. — " — LAPPED & D.R. 3/4 DIA.

BHD. LINERS 6" WIDE PARALLEL.



LIVINGSTONE & COOPER LTD.

0072011-007210-0294

Lowther

Mid. Section

No 156

Livingstone Vleoper.

S.S. "Muletia" Hull Rpt

Lowther

018.28773



47520-012600-002600



© 2020

Lloyd's Register
Foundation