

BOARD REPORT on the


Nakskov Skibsværft. Yard Nos. 51 and 52.

$$\text{Mld:- } \left\{ \begin{array}{l} 40.42^m \times 10.9^m \times 6.1^m \\ = 231.0' \times 35.76' \times 20.02' \end{array} \right.$$

$$\text{Fixed moulded draught desired} = 4.725^m = 15'-6''$$

- (1) The equivalent moulded depth of a full scantling flush decked ship with 50% excess sheer to give a moulded draught of 15'-6" for all seasons = 18'-8"
- (2) The equivalent moulded depth of a full scantling ship with actual crections (45.6% covered) and 50% excess sheer to give a moulded draught of 15'-6" for all seasons.  
= 14'-10 1/2"

Copy to Mr Potts.


 Lloyd's Register  
Foundation  
14-7-31.