

EQUIPMENT TONNAGE <i>Letter S.</i>										ANCHORS.									
Number of Certificate.	Anchors.	WEIGHT, EX. STOCK.			WEIGHT OF STOCK.			TEST, PER CERTIFICATE.			WEIGHT, REQ. BY RULE.			Description of Anchor.	Makers.	Where and when tested & Superintendent.			
		Cwts.	qrs.	lbs.	Cwts.	qrs.	lbs.	Tons.	cwts.	qrs.	lbs.	Tons.	qrs.	lbs.					
7162	1st Bower	45	2	4	Stockless			39	11	1	0	38	3	0	Baldt ✓	Baldt Anchor Co	Chester, Pa. 20/8		
7163	2nd "	44	3	14	"			39	3	1	21	38	3	0	"	"	J B Stevens		
7161	3rd "	29	1	24	"			28	5	0	0	32	2	0	"	"	"		
	Collective weight	119	3	13								110	0	0	Common	"	"		
7160	Stream	7	1	13	2	1	23	9	11	2	7	10	0	0		"	"		
7159	Kedge	6	0	3	1	2	7	8	5	0	8	5	0	0		"	"		
	2nd Kedge															"	"		

CHAIN CABLES.															HAWSERS AND WARPS.				
Number of Certificate.	Fathoms.	Size.	Test per Certificate. Tons.	Weight of Chain Cable.		Fathoms and Size per Rule.	Description.	Makers of Cables.	Where and when tested, and Superintendent.	Material.	Fathoms.	Size.	Test of Steel Wire Towline.	Fathoms.	Size.				
				Supplied.	Per Rule.														
CTY 283	240	2 1/2	81 1/4	585.31	397.36	240-1 1/2	Stud Link	J B Cam Co Troy, N.Y.	Troy, N.Y. 24/6/19 T.G. Dodd	TOWLINE	200	10		90					
										HAWSER	200	7		180					
										WARP	200	6		180					

Masts, Yards, &c., are in *good* condition, and sufficient in size and length.

Standing and Running Rigging is sufficient in size and *good* in quality.

Sails. *no sails* Suit of ✓ Sails, and the following spare sails ✓

Boats *2-24' lifeboats* Capstan *good* Rudder *good* Pumps *good*

Windlass, present state is *good*

Scuppers, &c.—What arrangements are there, beyond the scuppers on deck, for clearing upper deck of water, in case of a sea coming on board?

Cargo Hatchways.—How formed? *Strong Wood Coamings.* State size *N°1 11'-0"x14' N°2 14'-6"x14' N°3 10'*

If of extraordinary size, state how framed and secured?

What arrangement for shifting beams? *Fore & afters only Centre 12x14 4 wing 6"x11 1/2'*

Hatches, themselves, whether strong and efficient? *yes.* Main Hatchways.—State size *11'x14', 14'-6"x14', 10'*

Order for Special Survey, No. *49* 1st. When the Frame is completed *1918 9 June 22 Aug*

Date *✓* 2nd. When the Beams are put in, &c. *30 Oct 17 Dec 1919 Jan 20*

Order for Ordinary Survey, No. *✓* 3rd. When completed and before the plank be painted or payed *Feb 27, Mar 26, Apr 5, 17 May 27 June 3, 9, 23 July 22*

Date *✓*

No. *71* in Builder's Yard.

General Remarks. This vessel has been built under Special Survey in accordance with the Rules & approved plans & the workmanship & material are good throughout.

The fastening of the outside planking where iron is galvanised. The planking is fastened throughout with 4 dunnage in each double frame. The garboards are fastened horizontally with 1" galvanised iron bolts in every other frame space. The upper shanks of the planking the wales are edge bolted with 1" bolts in every alternate frame space.

The close truck ceiling is edge bolted from keelson to upper deck with 1 1/2" bolts in every frame space, in lieu of iron strapping.

The vessel has been salted as per Rule, except salting of beams.

It will be noted that the stream anchor, stream chain & tow line are so below the Rules requirements, but that the rest of the equipment is much heavier than required. The Owners desire the equipment noted above, as they consider it more suitable in their trade, & in view of the heavy anchors & chain cable supplied it is submitted that the present equipment might be accepted.

Present condition of Caulking of Bottom *good* Deck, *good* and Waterways *good*

If Sheathed, Doubled, Felted, Coppered, or Yellow Metalled *no* When last done *✓*

I am of opinion this Vessel should be Classed *12 A1 subject to surveys at 4+8 yrs old, with notation Salted*

The Amount of the Entry Fee ... £ *\$ 25.00*

Special ... £ *410.00*

Certificate ... £ *315.00*

Travelling Expenses, if any, £ *New York 10.00*

Fees applied for, *2 Sept 1919*

Received by me, *24.9.1919*

John S. Heck

Surveyor to Lloyd's Register of Shipping

Committee's Minute *New York SEP 23 1919*

Character assigned *+ 12 A1 subject (Horn)*

note: - as per Egl. R. S. Elec. Salted

+ d.m.c. 8.19

ALL CERTIFICATES VALID 11.11.19