

TO BE CLASSED LLOYDS 100A.1. FOR TOWING PURPOSES.

6 1/2" TYZACK SECTION.

4" x 3" ANGLES
8" x 6" ELM.
5 1/2" x 1" CONVEX.

10" / 20"

6" x 1/20" 5'-0" APART

3" x 3" x 8/20"

3" x 2 1/2" x 6/10"

13" x 1/20" EVERY FRAME

1 1/16" CHEQ PLATING.

8" x 8" x 1/4"

2 1/4" x 2 1/4" x 1/4" 30" APART

4 1/20"

Supported to Surveyor's satisfaction

Angle runner at head of keelson

✓ FRAMES:- 4" x 2 1/2" x 7/10" ANGLES 20" APART

✓ FLOORS:- 1 1/2" x 5/20" STRAIGHT ACROSS ON TOP 7/20" IN MACH. SPACE

✓ REV. FRAMES:- 2 1/4" x 2 1/4" x 5/10" ACROSS TOP OF FLOORS ONLY ^{double in 2nd B space} 4 1/2" x 4 1/2" x 9/20" ON ENGINE BEARRERS.

✓ BEAMS:- 4" x 3" x 6/20" ON EVERY FRAME

⊗ BULKHEADS 7/20" STIFFERS 3" x 2 1/2" x 7/10" 30" APART VERT. ~~48" HORIZ~~ ^{Collisions Bhd stiffened as per Rule}

✓ KEEL:- 6" x 1 1/8" STEM:- 5 1/2" x 1 1/8" ROUND FACE

✓ STERN FRAME:- 5 1/2" x 2 1/2"

✓ CENTRE KEELSON 6" x 3" x 8/20" DOUBLE B.A. FORWARD OF BOILER BHD ONLY

✓ SIDE KEELSONS 6" x 3" x 8/20" IN MACHINERY SPACE. SINGLE FORE & AFT.

✓ DECK PLATING:- STRINGER 3/8" REMAINDER 5/16" CHEQ WHERE SHEATHED OVER ACCOMMODATION. 4/16"

✓ BUNKERS:- 1/4" STIFFERS 3" x 2 1/2" x 1/4" 30" APART

✓ RUDDER:- SINGLE PLATE TYPE TO LLOYD'S REQUIREMENTS.

✓ EQUIPMENT TO LLOYD'S REQUIREMENTS.

✓ D.R.

7/20" - 6/20"

TWO PLATES AT FORE END 8/20"

5" x 4" x 8/20" ALL F & A.

J.R.

7/20" - 6/20"

6" x 6/20" B.P. 25'-0" AMIDSHIPS.

6/20"

6/20"

D.R.

7/20"

Pillars as per Rule & to Surveyor's satisfaction

17.5.13

ALL SCANTLINGS SUBJECT TO LLOYD'S APPROVAL.

Cochrane & Sons. Ltd
No 591

Midship Section

Dimensions,
80-0' x 20-5' x 10-5'

1/2 Lady Fredegar

Hull Report No: 26714



© 2020

Lloyd's Register
Foundation

009387-009400-0167