

# REPORT ON ELECTRIC FITTINGS.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

19 OCT 1933

Date of writing Report 18<sup>th</sup> Oct. 1933. When handed in at Local Office 18<sup>th</sup> Oct 1933. Port of BRISTOLNo. in Survey held at BRISTOL. Date, First Survey 19<sup>th</sup> Sept. Last Survey 22<sup>nd</sup> Sept 1933.  
Reg. Book. (Number of Visits 4)1920 on the Motor Barge "SEVERN CARRIER" Tons { Gross 109.62  
Net

Built at Bristol By whom built Chas Hill &amp; Sons Ltd. Yard No. 205. When built 1933

Owners Severn &amp; Banal carrying to Ltd. Port belonging to Bristol.

Electric Light Installation fitted by Messrs Chas Hill &amp; Sons Ltd. Contract No. - When fitted 1933

Is the Vessel fitted for carrying Petroleum in bulk Yes.

System of Distribution Twin Wiring throughout.

Pressure of supply for Lighting 24. volts, Heating 110. volts, Power - volts.

Direct or Alternating Current, Lighting Direct. Heating Power Direct.

If alternating current system, state frequency of periods per second -

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off Yes.

Generators, do they comply with the requirements regarding rating Yes., are they compound wound Yes.

are they over compounded 5 per cent. Yes., if not compound wound state distance between each generator

Where more than one generator is fitted are they arranged to run in parallel. - , is an adjustable regulating resistance fitted in series with each shunt field Yes.

Are all terminals accessible, clearly marked, and furnished with sockets Yes., are they so spaced or shielded that they cannot be accidentally earthed, short circuited, or touched Yes.

Position of Generators Starboard side. Engine Room.

Is the ventilation in way of the generators satisfactory Yes., are they clear of all inflammable material Yes.

if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the generators - and - , are the generators protected from mechanical injury and damage from water, steam or oil Yes.

are their axes of rotation fore and aft Yes.

Earthing, are the bedplates and frames of the generating plant efficiently earthed Yes. are the prime movers and their respective generators in metallic contact Yes.

Main Switch Boards, where placed Starboard side Engine Room for Heating circuits. Midship engine room casing for lighting circuits. If the generators and main switchboard are not placed in the same compartment, is each generator provided with a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard. -

Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes Yes.

are they protected from mechanical injury and damage from water, steam or oil Yes., if situated near unprotected woodwork or other combustible material, state distance of same horizontally from or vertically above the switchboards. - and -

are they constructed wholly of durable, non-ignitable non-absorbent materials Yes., is all insulation of high dielectric strength and of permanently high insulation resistance Yes.

with mica or micanite or other non-hygroscopic insulating material, and the slab similarly insulated from its framework Yes. and is the frame effectively earthed Yes.

Are the fittings as per Rule regarding: - spacing or shielding of live parts Yes., accessibility of all parts Yes., absence of fuses on back of board Yes., proportion of omnibus bars Yes., individual fuses to voltmeter, pilot or earth lamp None., connections of switches Yes.

Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switches Heating - 1 main


DP 60 amp. Flame &amp; Gas proof enclosed switch with Ammeter &amp; Voltmeter attached with DP fuses. Lighting - 1 DP 60 ampere Flame &amp; Gas proof enclosed switch with DP fuses.

Instruments on main switchboard 1 ammeters 1 voltmeters - synchronising device for paralleling purposes.

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system None.

Switches, Circuit Breakers and Fusible Cut-outs, do these comply with the requirements of the Rules Yes.

Joint Boxes Section and Distribution Boards, is the construction, protection, insulation, material, and position of these as per rule Yes.



© 2021

Lloyd's Register Foundation



Cables: Single, twin, concentric, or multicore *Single* are the cables insulated and protected as per Tables IV or V of the Rules *Yes*.

Fall of Pressure, state maximum between bus bars and any point of the installation under maximum load *2 Volts*.

Cable Sockets and other connections, are the ends of all cables having a sectional area of 0.04 square inch and above provided with soldering sockets *Yes*.

Paper Insulated Cables. If cables are paper covered, is the dielectric at the exposed ends of the conductor protected from moisture by being suitably sealed with insulating compound *Yes*.

Cable Runs, are the cables fixed as far as possible in accessible positions not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical damage *Yes*.

Support and Protection of Cables, state how the cables are supported and protected *banduit throughout*.

If cables are run in wood casings, are the casings and caps secured by screws —, are the cap screws of brass —, are the cables run in separate grooves —. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII —.

Refrigerated Chambers, if lights are fitted, are the cables and fittings in accordance with the special requirements —.

Joints in Cables, state if any, and how made, insulated, and protected *Gas & Flame proof junction boxes. joints made by Ramee connectors protected with pure rubber & black tape*.

Watertight Glands and Deck Tubes, are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands *Yes*.

Bushes in Beams and Non-watertight Partitions, where unarmoured cables pass through beams and non-watertight partitions, are the holes efficiently bushed *Yes* state the material of which the bushes are made —.

Earthing Connections, state what earthing connections are fitted and their respective sectional areas *all portable lights fitted with earth wire of 11.012 nominal area .001*.

are their connections made as per Rule *Yes*.

Alternative Lighting, are the groups of lights in the propelling machinery space arranged as per Rule —.

Emergency Supply, state position and method of control of the emergency supply and how the generator is driven —.

Navigation Lamps, are these separately wired *Yes*, controlled by separate switch and separate fuses *Yes*, are the fuses double pole *Yes*, are the switches and fuses grouped in a position accessible only to the officers on watch *Yes*, has each navigation lamp an automatic indicator as per Rule *none*.

Secondary Batteries, are they constructed and fitted as per Rule *Yes*.

Fittings, are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight *Yes*, are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected *No*, are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected *all fittings Flame & Gas proof*, how are the cables led *banduit*, where are the controlling switches situated *in Gas proof boxes in Engine Room, deck & accommodation*.

Searchlight Lamps, No. of —, whether fixed or portable —, are their fittings as per Rule —.

Arc Lamps, other than searchlight lamps, No. of —, are their live parts insulated from the frame or case —, are their fittings as per Rule —.

Motors, are their working parts readily accessible —, are the coils self-contained and readily removable for replacement —, are the brushes, brush holders, terminals and lubricating arrangements as per Rule —, are the motors placed in well-ventilated compartments in which inflammable gases cannot accumulate and clear of all inflammable material —, are they protected from mechanical injury and damage from water, steam or oil —, are their axes of rotation fore and aft —, if situated near unprotected woodwork or other combustible material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type —, if not of this type, state distance of the combustible material horizontally or vertically above the motors — and —.

Control Gear and Resistances, are the generator field and motor speed regulators, starters and controllers constructed and fitted as per Rule *Yes*.

Lightning Conductors, where lightning conductors are required, are these fitted as per Rule —.

Ships carrying Oil having a Flash Point less than 150° F. Have the special requirements of the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and fittings *Yes*, If portable lamps for use in dangerous spaces are supplied, are they of a type approved by the Home Office *Yes*.

PARTICULARS OF GENERATING PLANT.									
DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE.		
		Kilowatts.	Volts.	Ampères.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.	
MAIN ...	1	2½	110.	22.5		Paper Atomic Engine	Heavy Oil	Above 150°	
AUXILIARY ...						coupled to Compton Pumping 4 pps.			
EMERGENCY ...									
ROTARY TRANSFORMER									

GENERATOR, LIGHTING AND HEATING CONDUCTORS.									
DESCRIPTION.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT. AMPERES.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
	No. per Pole.	Total Effective Area per Pole Sq. Ins.	No.	Diameter.	In Circuit.	Rule.			
MAIN GENERATOR ...	1	.0225	7	.064	18.2	46.✓	12	Rubber	banduit.
EQUALISER CONNECTIONS									
AUXILIARY GENERATOR...									
EMERGENCY GENERATOR									
ROTARY TRANSFORMER } MOTOR GENERATOR...									
ENGINE ROOM...	1	.002	3	.029	3	7.8✓	30	Rubber	banduit.
BOILER ROOM...									
AUXILIARY SWITCHBOARDS									
ACCOMODATION Aft...	1	.002	3	.029	2	7.8✓	30	Rubber	banduit.
Fore...	1	.002	3	.029	2	7.8✓	110	Rubber	banduit.
Forward...	1	.007	7	.036	18.2	24✓	40	Rubber	banduit.
WIRELESS									
SEARCHLIGHT	1	.002	3	.029	1	7.8✓	100	Rubber	banduit.
MASTHEAD LIGHT	1	.002	3	.029	2	7.8✓	20	Rubber	banduit.
SIDE LIGHTS	1	.002	3	.029	1	7.8✓	20	Rubber	banduit.
COMPASS LIGHTS									
POOP LIGHTS									
CARGO LIGHTS									
ARC LAMPS									
HEATERS	1	.003	3	.036	10.2	12✓	120	Rubber	banduit.

MOTOR CONDUCTORS.										
DESCRIPTION.	No. of Motors.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT. AMPERES.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
		No. Per Pole.	Total Effective Area per Pole Sq. Ins.	No.	Diameter.	In Circuit.	Rule.			
BALLAST PUMP										
MAIN BILGE LINE PUMPS										
GENERAL SERVICE PUMP										
EMERGENCY BILGE PUMP										
SANITARY PUMP										
CIRC. SEA WATER PUMPS										
CIRC. FRESH WATER PUMPS...										
AIR COMPRESSOR										
FRESH WATER PUMP										
ENGINE TURNING GEAR...										
ENGINE REVERSING GEAR										
LUBRICATING OIL PUMPS										
OIL FUEL TRANSFER PUMP...										
WINDLASS										
WINCHES, FORWARD										
WINCHES, AFT										
STEERING GEAR—										
(a) MOTOR GENERATOR...										
(b) MAIN MOTOR										
WORKSHOP MOTOR										
VENTILATING FANS										



All Conductors are of annealed copper conforming to British Standard Specification No. 7.

The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.

The foregoing is a correct description.

CHARLES HILL & SONS, LTD.

*Alauw Pech*

Electrical Engineers.

Date

16 OCT 1933

DIRECTOR

#### COMPASSES.

Distance between electric generators or motors and standard compass

Distance between electric generators or motors and steering compass

The nearest cables to the compasses are as follows:—

A cable carrying 1 Ampères ~~feet from standard compass~~ into ~~feet from steering compass~~.

A cable carrying Ampères feet from standard compass feet from steering compass.

A cable carrying Ampères feet from standard compass feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power *compasses not adjusted*

Has the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted

The maximum deviation due to electric currents was found to be degrees on course in the case of the standard compass, and degrees on course in the case of the steering compass.

CHARLES HILL & SONS, LTD.

*Alauw Pech*

DIRECTOR

Builder's Signature.

Date

16 OCT 1933

Is this installation a duplicate of a previous case *no*. If so, state name of vessel

General Remarks (State quality of workmanship, opinions as to class, &c.)

*This installation of electric fittings has been found under special survey. The materials & workmanship are found to be according to the Rules.*

*It has been tried & examined under working conditions with satisfactory results & is eligible in my opinion for notation in the Register Book.*

**It is submitted that  
this vessel is eligible for  
THE RECORD.**

*Elec. Sign-*

*24  
7/11/33.*

Total Capacity of Generators *2½* Kilowatts.

The amount of Fee ... £ 5 : 0 : 18<sup>th</sup> Oct. 1933.

Travelling Expenses (if any) £ : : When received, 15.11.1933

Committee's Minute

Assigned

*Elec. Sign*

*John L. Guymre*

Surveyor to Lloyd's Register of Shipping.

Im. 11.20.—Transfer.  
(The Surveyors are requested not to write on or below the space for Committee's Minute.)



© 2021

Lloyd's Register  
Foundation