

of "Kurmack."

Lon. Rpt. 86308.

This vessel was built in 1912 & classed with the Germanischer Lloyd.

A report on the machinery was received from the Antwerp Surveyors on the 10th ultimo. together with the plans of the boilers & the pumping arrangement.

The scantlings of the boilers as shown on the plan are such as might be approved for the original working pressure of 13.5 Kg. Cm.² = 192 pounds.

The pumping arrangement complies with the Rules at the time when the vessel was built.

The machinery has been opened out, examined & found good & complies with the Rules, except that no mention is made in the report of the required spare gear. The boiler survey was held at Glasgow in 2.22.

To complete the survey the Superheater & auxiliary steam pipes require to be tested & examined & the spare gear required by the Rules seen aboard.

It is submitted that this vessel is eligible for THE RECORD. LMC-MS 1.23.

S 3.22.CL. 1921b. BS 2.22. FD.

T. 3 Cy. 28". 45" & 74". - 54". 510 NH.

3SB 9cf. GS225. HS6943.

Subject to the Survey being completed as above.

The Owners Superintendent states that the survey will be completed on the vessels' return in about 13 months. when also the boiler survey, due 2.23, will be held.

JRH

MD.
1/2/23.



© 2020

Lloyd's Register
Foundation

009702-009710-0186

009702-009710-0003 12