

COPY

Lloyd's Register of Shipping.

Port Kobe.

5th November, 1940.

DAMAGE "B"

This is to Certify that

T. Kunishi,

the undersigned Surveyor to this Society did at the request of the Owners, survey the

S.S. "KOHUKU MARU",

5825 tons gross, of Hasidate,

on the 12th October, 1940, and subsequently, whilst the vessel lay in dry dock at Messrs. Osaka Iron Works, Innoshima, for the purpose of ascertaining the nature and extent of damage stated to have been caused by the vessel striking some submerged object on the 2nd October, 1940, whilst on a voyage from Muroran to Osaka.

For further particulars see Log Books.

The undersigned upon examination,

FOUND

RECOMMENDED

In way of No.1 Oil Fuel Double Bottom Tank.

No.2 keel plate and No.3 plate in "A" strake, on port side, slightly indented.

To be released, faired in place and reriveted.

A number of bottom rivets, slack & seams, leaky in several places.

Slack rivets to be renewed and leaky seams to be recaulked.

It was further recommended that all disturbed work be recoated as necessary and the No.1 double bottom tank be tested and proven tight.

(continued) T.K.

Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:—
The Committees of the Society use their best endeavours to ensure that the functions of the Society are executed, it is to be understood that neither the Society nor any Member of any of its Committees is under any liability whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Committees, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or omission of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."

Lloyd's Register
Foundation
00472 (004724)135

COPY

(2)

S/S "HOHUKU HARU".
DAMAGE "B"

Kobe, 5th November, 1940.

The foregoing recommendations were made in order to place the vessel in as good a condition as before the damage sustained and have now been satisfactorily completed.

T. Remick
Surveyor to Lloyd's Register.

Fee & expenses as per account.



© 2021

Lloyd's Register
Foundation

009 721-09729-035