


28.4  
5.7  
M.S. - ARIMASAN MARU  
Await reply to cablegram of 29.12

Further communication to be  
sent to Kobe as survey required,  
if B & class is specified  
(see foot of edr. 22.12.41)




© 2020

Lloyd's Register  
Foundation

009805-009814-005.1

arrangements and equipment are found to be in accordance  
with the requirements of the Rules.



An Oerlikon gun is to be fitted on a raised platform on the upper deck aft in the undermentioned vessels, and arrangements are to be in accordance with Drawing D.N.C.29/A/663. In order to compensate for topweight the protection shelter immediately forward of the exhaust funnel on the bridge deck is to be landed and ten tons of non-magnetic slag ballast is to be fitted as low as possible between frames under the battery room flat and in engine room. The ballast should be cemented in and the following precautions taken :-

- (1) Coat surface of timber with tar.
- (2) Dust thickly with Portland cement.

2. Bulk ammunition is to be stowed in a magazine locker on the upper deck abreast the platform. Two ready-use lockers are to be fitted on the platform.

3. The vessels concerned are as follows :-

M.M.S. 1, 5-9, 14-19, 22-31, 36-38, 40-49,  
53-89, 91-92, 102-118, 137, 139-140, 149-150, 165, 167-  
173, 175-179, 181, 183, 202, 204-206, 213, 216, 218,  
220-221, 224-225, 228-229, 233, 236, 261, 268.

© 2020

Library Register  
Foundation