

J. 74. C

FREEBOARD VERIFICATION FORM FOR JAPANESE STEAMERS.

When received in Kobe Office.....

Port NAGASAKI.

Vessel's Name Steel Twin Screw Motor Vessel "KINAI MARU".

Official No. _____ No. in Reg. Book 75566

Port of Registry Osaka.

Wood or Steel Steel. State whether Classed by Lloyd's Register Yes

Name of Owners Osaka Shosen Kabushiki Kaisha.

Date of Assignment Letter 23rd May 1930 Date of Verification 31st May 1930.

I have to report that the Freeboard from the centre of disc to the top of the freeboard deck line, and the lines in connection therewith, as given below, assigned by the Society to this vessel, have been correctly marked on the vessel's sides, in accordance with the printed instructions:—

Vertical distance from the point of intersection of the extended line of the upper surface of **Wood deck** of the **Upper** deck at midlength of vessel with the outside of shell-plating, to the upper edge of the horizontal line indicating the Freeboard deck

92.2 inches measured down ward 7-8 1/4

Vertical distance from the upper edge of the horizontal line indicating the Freeboard deck to the Centre of the Disc

64.1 inches measured downward 5-4

Vertical distance from the Centre of the Disc to the Fresh Water Load Line

7.3 inches measured upward

Vertical distance from the Centre of the Disc to the Tropical Load Line

6.4 inches measured upward

Vertical distance from the Centre of the Disc to the Winter Load Line

6.4 inches measured downward

Vertical distance from the Centre of the Disc to the Winter North Atlantic Load Line

- inches measured downward

George Anderson Surveyor.

Particulars for Record in Register Book:-

Moulded depth	<u>40</u> ft <u>9</u> ins. ;	Freeboard	<u>5</u> ft <u>4.1</u> ins. <u>(5-4)</u>
* Draught (bottom of keel)	<u>28</u> ft <u>2.08</u> ins. <u>28-2</u>		
* Deadweight capacity of cargo & bunkers	<u>About.</u>	<u>9,930.</u>	Tons
* Cubic capacity permanent bunkers	"	<u>76,446.</u>	cu.ft.
* Cubic capacity cargo grain	"	<u>617,607.</u>	cu.ft.
* Cubic capacity cargo bale	"	<u>572,029.</u>	cu.ft.

Noted for posting _____

*Particulars Supplied by Builders or Owners.

G.W.B.
23-6-30

Lloyd's Register Foundation