

REPORT ON BOILERS. SEA. No. 3453

Received at London Office 5-AUG 1942

Date of writing Report 19 When handed in at Local Office 19 Port of SEATTLE, WASHINGTON

No. in Survey held at Seattle, Washington Date, First Survey October 1st Last Survey December 30th 1941

Reg. Book. on the Todd-California Shipbuilding Corp., Yard No. 19 "Ocean Vista" (Number of Visits 22) Tons { Gross 717.4 Net 427.2

Master Built at Richmond, Calif. By whom built Todd-Calif. Shipbldg. Corp. When built 1941

Engines made at Hamilton, Ohio. By whom made General Machinery Corp. When made 1942

Boilers made at Seattle, Wash. By whom made Puget Sound Machinery Depot When made 1941

Registered Horse Power 505 Owners British Government Port belonging to London

MULTITUBULAR BOILERS—MAIN, AUXILIARY OR DONKEY—Manufacturers of Steel Lukens, Carnegie-Illinois, S. Cos.

Letter for record S Total Heating Surface of Boilers 7140 sq.ft. Is forced draft fitted No. and Description of

Boilers One- Scotch, Single Ended Working Pressure 220 lbs Tested by hydraulic pressure to 380 lbs Date of test Dec. 18

P.S.M.D. No. of Certificate No. 7 Can each boiler be worked separately Area of fire grate in each boiler 52 sq.ft. No. and Description of

safety valves to each boiler Area of each valve Pressure to which they are adjusted

Are they fitted with easing gear In case of donkey boilers, state whether steam from main boilers can enter the donkey boiler

Smallest distance between boilers or uptakes and bankers or woodwork Outs. Max dia. of boilers 14' 9" Length 11' 9"

Material of shell plates Steel Thickness 1-13/32" Range of tensile strength 75,000 Are the shell plates welded or flanged No

Description of riveting: cir. seams D.R. long. seams T.R.D.B.S. Diameter of rivet holes in long. seams 1 1/2" Pitch of rivets 5" & 10"

Width of butt straps 22-1/8" Per centages of strength of longitudinal joint 93.4 Working pressure of shell by 85.0

Weight of boiler 221.2 lbs Size of manhole in 3 - 12" x 16" Size of compensating ring Flanged No. and Description of Furnaces in each

Boiler 3-Corrugated Material Steel Outside diameter 44-9/16" Length of plain part 4 1/2' top 7-13/16" Thickness of plates 21/32" crown 21/32" bottom 7-13/16" bottom 21/32"

Description of longitudinal joint Forge weld No. of strengthening rings - Working pressure of furnace by the rules 230 lbs Combustion chamber 9" x

Material Steel Thickness: Sides 25/32" Back 25/32" Top 25/32" Bottom 25/32" Pitch of stays to ditto: Sides 10-3/16" Back 9" x 9"

Area supported by each stay 441 sq. ins. Working pressure by rules 245 # Material of Front plates at bottom Steel Thickness 1-1/32" Material of

Number back plate Steel Thickness 1-1/32" Greatest pitch of stays 9" x 9" Working pressure of plate by rules 232 Diameter of tubes 3"

Pitch of tubes 4-1/4" Material of tube plates Steel Thickness: Front 1-1/32" Back 13/16" Mean pitch of stays 9-7/16" Pitch across wide

Inter spaces 14 1/2" Working pressures by rules 232 lbs Girders to Chamber tops: Material Steel Depth and thickness of

Order at centre (x 7/8") Length as per rule 34" Distance apart 11" Number and pitch of Stays in each 3 - 7-5/8"

Working pressure by rules 229 Steam dome: description of joint to shell - % of strength of joint -

Diameter - Thickness of shell plates - Material - Description of longitudinal joint - Diam. of rivet holes -

Pitch of rivets - Working pressure of shell by rules - Crown plates - Thickness - How stayed -

SUPERHEATER. Type - Date of Approval of Plan - Tested by Hydraulic Pressure to -

Date of Test - Is a Safety Valve fitted to each Section of the Superheater which can be shut off from the Boiler -

Diameter of Safety Valve - Pressure to which each is adjusted - Is Easing Gear fitted -

VERTICAL DONKEY BOILER— No. - Description - Manufacturers of steel -

Made at - By whom made - When made - Where fixed - Working pressure -

Tested by hydraulic pressure to - Date of test - No. of Certificate - Fire grate area - Description of safety valves -

Description of safety valves - Area of each - Pressure to which they are adjusted - If fitted with easing gear - If steam from main boilers can

Enter the donkey boiler - Dia. of donkey boiler - Length - Material of shell plates - Thickness - Range of tensile

Strength - Descrip. of riveting long. seams - Dia. of rivet holes - Whether punched or drilled - Pitch of rivets -

Description of plating - Per centage of strength of joint - Rivets - Working pressure of shell by rules - Thickness of shell crown plates -

Radius of do. - No. of Stays to do. - Dia. of stays - Diameter of furnace Top - Bottom - Length of furnace -

Thickness of furnace plates - Description of joint - Working pressure of furnace by rules - Thickness of furnace crown -


Radius - Radius of do. - Stayed by - Diameter of uptake - Thickness of uptake plates -

Thickness of water tubes -

The foregoing is a correct description,
Puget Sound Machinery Depot Manufacturer.
By [Signature]

During progress of work in shops -- Oct: 1, 18, 28, 31. Nov: 5, 9, 13, 17, 24, 26, 28
 Dec: 1, 2, 3, 7, 11, 12, 18, 22, 27, 29, 30.
 Total No. of visits 22

Is the approved plan of main boiler forwarded herewith -



GENERAL REMARKS (State quality of workmanship, opinions as to class, &c.)

The Scotch marine single ended boiler herein mentioned has been built under special survey and in accordance with the Rules and approved plan. The materials tested as required by the Rules and together with workmanship, found good throughout. This boiler has now been forwarded to Todd-California Shipbuilding Corp., Richmond, California, stated to be fitted on board their Hull No. When this has been done in accordance with the Rules, to the Surveyor's satisfaction, the boiler will be eligible in my opinion to receive the notation 220 lbs in the Register Book.

Certificate (if required) to be sent to
(The Surveyors are requested not to write on or below the space for Committee's Minute.)

	When applied for.	When received.
The amount of Entry Fee .. £	: : : 19.....	
Special \$108.61 :		
Donkey Boiler Fee £	: : : 19.....	
Travelling Expenses (if any) £	\$4.00: : : 19.....	

Committee's Minute NEW YORK JUL 22 1942

Assigned See Richmond Rpt. No. 19 H.S.

W. Smith
Engineer Surveyor to Lloyd's Register of Shipping

