

Yld. 1925.

Lloyd's Register of Shipping.

23 FEB 1943

Ship's Name "FORT SLAVE"

Official No. 168382.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

The following alterations were effected:-

In way of new accommodation amidships, on main deck:- new companionways fitted 1 p & 1 s, on shelter deck, at p & s after corners of amidships house; substantially constructed of steel plates and closed by stout hinged wood doors fitted with spring lock. Sills 22" high.

1 additional sanitary discharge valve fitted starboard side of main deck, fitted with storm valve and screw down valve controlled from upper deck.

In way of new accommodation on main deck aft:- existing companionway removed from tonnage well hatch on shelter deck, and enlarged companionway fitted, substantially constructed of steel plates and having 2 entrances closed by stout wood doors fitted with spring locks. Sills 24" high.

5 additional sidelights fitted on starboard side in main decks, with hinged dead lights. Additional ventilators fitted on shelter deck 3 starboard 1 port, each 7" diameter, coamings 3'-6" high, closed by wood plugs and canvas covers.

A.W.B. Edwards

Surveyor to

Lloyds Register of Shipping

Hull 17/2/43.

*80B
5-11-43*

