

Rpt. 5a. ---
Rpt. 5a. ---

REPORT ON BOILERS.

No. 5644

23 JUL 1942

Received at London Office

Date of writing Report 25th May 1942 When handed in at Local Office 26th May 1942 Port of MONTREAL, P.Q.

No. in Survey held at MONTREAL, QUE.
Reg. Book.

Date, First Survey 16th July, 1941. Last Survey 20th April 1942.

on the Steel Single Screw Steamer, "FORT TADOUSSAC"

(Number of Visits 35) Gross 7128.86
Tons Net 4258.94

Built at LEVIS, P.Q., By whom built DAVIE SHIPBUILDING & REPAIRING CO. LIMITED Yard No. 531 When built 1942.

Engines made at LACHINE, P.Q. By whom made Dominion Engineering Company Engine No. 1 When made 1941

Boilers made at LACHINE, P.Q. By whom made Dominion Bridge Co. Ltd. Boiler No. B914C1 When made 1941
PI
SI

Nominal Horse Power 504

Owners

Port belonging to

MULTITUBULAR BOILERS—MAIN, ~~AUXILIARY~~ OR ~~DONKEY~~

Manufacturers of Steel Bethlehem Steel, Dominion Foundry & Steel, Lukens

(Letter for Record (S) ✓)

Total Heating Surface of Boilers 2380 square feet $\times 3 = 7140$ Is forced draught fitted Yes

Coal or Oil fired Coal

No. and Description of Boilers Three Single Ended Multitubular

Working Pressure 220 lbs. per sq. in.

Tested by hydraulic pressure to 380 lbs. per sq. in. Date of test 5/11/41 No. of Certificate 1 Can each boiler be worked separately Yes

Area of Firegrate in each Boiler 51 sq. ft. No. and Description of safety valves to each boiler One double spring safety valve

Area of each set of valves per boiler { per Rule 8.87 sq. in. 72.67 for ordinary valves
as fitted 7.95 " " Pressure to which they are adjusted 220 Are they fitted with easing gear Yes

In case of donkey boilers, state whether steam from main boilers can enter the donkey boiler ---

Smallest distance between boilers or uptakes and bunkers or woodwork 6'0" Is oil fuel carried in the double bottom under boilers No

Smallest distance between shell of boiler and tank top plating 2'0" Is the bottom of the boiler insulated Yes

Largest internal dia. of boilers 14'-6-3/16" Length 11'-9" Shell plates: Material Steel Tensile strength 29/33 tons

Thickness 1-13/32" Are the shell plates welded or flanged No Description of riveting: circ. seams { end D.R.
inter. ---

long. seams T.R. zig zag Diameter of rivet holes in { circ. seams 1 1/2
long. seams 1 1/8" Pitch of rivets { 4-3/16
10-1/16

Percentage of strength of circ. end seams { plate 64.0
rivets 47.0 Percentage of strength of circ. intermediate seam { plate ---
rivets ---

Percentage of strength of longitudinal joint { plate 85.6
rivets 92.9 combined 88.7

Thickness of butt straps { outer 1-3/32"
inner 1-7/32" No. and Description of Furnaces in each Boiler Three Morrison corrugated type -

Material Steel Tensile strength 26/30 tons Smallest outside diameter 41" ? 4 1/2

Length of plain part { top ---
bottom --- Thickness of plates 21/32" Description of longitudinal joint lap weld

Dimensions of stiffening rings on furnace or c.c. bottom ---

End plates in steam space: Material O.H. STEEL Tensile strength 26/30 tons Thickness 1-7/16" Pitch of stays 21" x 21"

How are stays secured Inside and Outside Nuts

Tube plates: Material { front O.H. Steel
back O.H. Steel Tensile strength { 26/30 tons Thickness { 31/32"
13/16"

Mean pitch of stay tubes in nests 8 1/4 = 9.4375" Pitch across wide water spaces 14 1/2"

Girders to combustion chamber tops: Material O.H. STEEL Tensile strength 29/33 tons Depth and thickness of girder

at centre 2 @ 10 1/4 x 7/8" Length as per Rule 34" Distance apart 11" No. and pitch of stays

in each 3 @ 7-5/8" Combustion chamber plates: Material O. H. STEEL

Tensile strength 26/30 tons Thickness: Sides 25/32" Back 23/32" Top 25/32" Bottom 25/32"

Pitch of stays to ditto: Sides 10-3/16 x 9" Back 9" x 9" Top 11" x 7-5/8" Are stays fitted with nuts or riveted over Nutted

Front plate at bottom: Material O.H. STEEL Tensile strength 26/30 tons

Thickness 31/32" Lower back plate: Material O.H. STEEL Tensile strength 26/30 tons Thickness 29/32"

Pitch of stays at wide water space 11 1/2" x 9" Are stays fitted with nuts or riveted over Nutted

Main stays: Material O.H. STEEL Tensile strength 28/32 tons

Diameter { At body of stay, 3 1/2"
or
Over threads --- No. of threads per inch 6

Screw stays: Material O.H. STEEL Tensile strength 26/30 tons

Diameter { At turned off part, ---
or
Over threads 1 3/4" No. of threads per inch 9

© 2021

Lloyd's Register
Foundation

009994-010003-0223

Are the stays drilled at the outer ends No ✓ Margin stays: Diameter { At turned off part, 2" or Over threads 2" ✓

No. of threads per inch 9 ✓

Tubes: Material STEEL External diameter { Plain 3" ✓ Stay 3" ✓ Thickness { 8 SWG ✓ 5/16" & 3/8" ✓ No. of threads per inch 9 ✓

Pitch of tubes 10-5/8" x 8 1/4" Manhole compensation: Size of opening in shell plate None Section of compensating ring --- No. of rivets and diameter of rivet holes ---

Outer row rivet pitch at ends --- Depth of flange if manhole flanged 4 1/4" in back end plate ✓ Steam Dome: Material None

Tensile strength --- Thickness of shell --- Description of longitudinal joint ---

Diameter of rivet holes --- Pitch of rivets --- Percentage of strength of joint { Plate --- Rivets ---

Internal diameter --- Thickness of crown --- No. and diameter of stays --- Inner radius of crown ---

How connected to shell --- Size of doubling plate under dome --- Diameter of rivet holes and pitch of rivets in outer row in dome connection to shell ---

Type of Superheater Smoke tube ✓ Manufacturers of { Tubes National Tube Co., Penna. ✓ Steel forgings The Superheater Company, Sherbrooke, P.Q. ✓ Steel castings " " " " " ✓

Number of elements 58 ✓ Material of tubes S.D. STEEL ✓ Internal diameter and thickness of tubes .69" - .095" ✓

Material of headers O.H. STEEL ✓ Tensile strength 33.5 tons ✓ Thickness 1-1/8" min. ✓ Can the superheater be shut off and the boiler be worked separately Yes Is a safety valve fitted to every part of the superheater which can be shut off from the boiler Yes

Area of each safety valve 3.1416 in. ✓ Are the safety valves fitted with easing gear No. ✓

Pressure to which the safety valves are adjusted 220 lbs. per sq. inch. ✓ Hydraulic test pressure: tubes 1500 lbs. per sq. in. forgings and castings 700 lbs. per sq. in. and after assembly in place 400 lbs. per sq. in. Are drain cocks or valves fitted to free the superheater from water where necessary Yes

Have all the requirements of Sections 14 to 22 inclusive for boilers been complied with Yes ✓

The foregoing is a correct description,
DOMINION BRIDGE CO., LIMITED Manufacturer.
A. J. Hall

Dates of Survey { During progress of work in shops 16, 29 July; 4, 18 Aug; 2, 10, 29 Sept; 1, 7, 16, 22, 28 Oct; 3, 5, 7 Nov. ✓ Are the approved plans of boiler and superheater forwarded herewith (If not state date of approval.) ---

while building { During erection on board vessel 13, 16, 17, 29 Dec; 5, 14, 19, 23 Jan; 9, 13, 19, 27 Feb; 6, 11, 18, 24, 31 Mar; 7, 13, 20 Apr. ✓ Total No. of visits 35.

Is this Boiler a duplicate of a previous case --- If so, state Vessel's name and Report No. ---

GENERAL REMARKS (State quality of workmanship, opinions as to class, &c.)

These BOILERS have been constructed under special survey in accordance with the approved Plans. The materials and workmanship are good. They were tested hydrostatically at 380 lbs. per square inch pressure, and found good. They have been properly installed, and the safety valves adjusted under steam at 220 lbs. per square inch, and washers noted.

NOTE: The longitudinal seams of the front and back end plates of these BOILERS have been welded by the Union Melt Process. For further particulars see Approved Plans and results of tests.

Survey Fee ... £ \$ 150.00

Travelling Expenses (if any) £ To be :

Exps. Inclusive Ch'd at London

When applied for, 19

When received, 19

A. J. Hall & H. J. Daunders.
 Engineer Surveyor to Lloyd's Register of Shipping.

Committee's Minute

Assigned

FRI. 7 AUG 1942

See Int. No. 5644



© 2021

Lloyd's Register
 Foundation