

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

GLASGOW REPORT No. FBD. 561

ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name "CAIRNGORM"

Official No. 165950


Port of Registry Glasgow

This ship has been under survey at Bowling

on 7th September, 1956 and the following alterations to the conditions of assignment of loadlines have now been effected/~~found~~:-

All hatch beams at Nos.1 and 2 hatches renewed at this time having 13" x .38" webs with 3.1/2" x 3.1/2" x .44" top and bottom angles. In lieu of rolling beams, as originally fitted, fabricated sockets have now been provided attached to the horizontal and vertical bulb angles of the hatch coamings fixing the beams in position on a 3.1/2" landing. Locking bolts have also been provided.

The fore and aft retaining flat bar used in conjunction with the rolling beams has now been removed.




Surveyor to Lloyd's Register.

(T.S.FATKIN)

Noted
m
11.9.61

A copy of this Report has been placed on board.



© 2021

Lloyd's Register
Foundation

010012-010023-0272