

BOARD REPORT on the

S.S. "Mary Birch"

W.H. Warren & Co 127

Hull report 29857

m^{rs} Aspinall

It is submitted the Surveyor be informed that the height of raised quarter deck should be measured relative to the upper deck at the middle of the length and the sheers should be measured from a line parallel to raised quarter deck. He should forward an amended report giving the sheers at after end and at $\frac{1}{4}$ th length from aft relative to the above parallel line. He should further be informed that the sheer used in the correction for depth for tonnage coefficient is the gradual sheer at ends, and that the length of erections used in the correction for iron deck and round of beam is the total length covered irrespective of height of erections.

G.M.

W.H.

21.3.17

010037-010045-0228