



# LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

10, Commerce Chambers, High Street, Ipswich

Telephone: Ipswich 2/18/52518

Reference

Classn (S).

RECEIVED

9 - FEB 1960

8th February 1960.

Dear Sir,

Barge "BLACKBIRD C"

We are in receipt of your letter dated 1st February regarding our report C.11 on the above vessel, and have to confirm as follows:-

- 1). The thickness of ventilators coamings being .30"
- 2). Manholes on freeboard deck 18" x 12" closed with flat plate covers  $\frac{3}{8}$ " thick secured by  $\frac{5}{8}$ " diameter studs at  $2\frac{1}{2}$ " centres on watertight rubber joint.

- 3). Tank lids on trunk top fastened with screwed toggles maximum spacing 18"

Hinged W.T. Steel covers on freeboard deck to dry peak and chain locker secured with screwed toggles maximum spacing 12".

Yours faithfully,  
The Surveyors.  
per:-

The Secretary.  
LONDON.



© 2020

Lloyd's Register  
Foundation

010137-010149-0005



SR.

REES BOARD

*M*

29/2/60

Noted

to note

*Mr Fryer*

Noted

c11. K.R.

1/3/60



© 2020

Lloyd's Register  
Foundation