

COPY

LLOYD'S REGISTER OF SHIPPING



Blackburne
James W. Blackburne (Manchester) No. 1185
Specific Report No. 140777

Port MANCHESTER.

C.5205.

26th February, 1959.

This is to Certify that

R.C. CLAYTON,

the undersigned Surveyor to this Society did at the request of Messrs. David McClure Limited, attend at their Works at Stockport on the 20th February, 1959, and subsequently, for the purpose of inspecting and testing the following Generators made to Order No. 202500 of Messrs. R.A. Lister & Co. Limited, Dursley, Gloucestershire.

Two - 7 kW., 1800 R.P.M., 110 volt, enclosed ventilated, compound wound, marine type Generators, Serial Nos. 20593A and 20593B.

Each of these generators was run on full load until the temperatures were constant and the temperature rises were then found to be within the specified limits of 35°C.

The compounding was checked hot and overloads up to 50% were applied and the commutation found good.

Finally, the windings were subjected to insulation resistance and pressure tests at 2 K.V.

All these tests were satisfactory and, as far as could be seen, the materials and workmanship employed have been good and sound.

For identification purposes the generator yokes were stamped:-

L.R. R.C.C. with date.

SURVEYOR TO LLOYD'S REGISTER OF SHIPPING.

Fee: £7/7/0d.

Exp: -/9/0d.

Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:-

"While the Committees of the Society use their best endeavours to ensure that the functions of the Society are properly performed, it is to be understood that neither the Society nor any Member of any of its Committees is under any circumstances liable to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of its Committees or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."