

010219-010228-0321

Ship's name **AKAMAS**

Port

HNA.

20 DEC 1963

No. 2100

Last survey date 22-11-63

Class is subject to -

- (1) M/E bedplate (Abolished 1/63) being re-examined by end of 10/63.
 (2) the propeller, underwater fastenings and sea valves being specially examined at the next D-V.

MBS due 9/63, now partly held. *amended*

SRL Item (i) examined, found to remain efficient and to be re-examined by 11/64 (12 was laid)

The Surveyor reports when examining the Starboard main boiler, a number of plain tubes found to be leaking, four tubes fitted with stoppers, four superheater elements leaking, four air heater tubes plugged and many air heater tubes thin, some CC stops worn. As no facilities available for repairs, the leaking tubes expanded and the defective elements welded, and leak hydro tested. The boiler to be again examined and repairs to the wasted CC stops and air heater tubes before completion of B.S.

It is submitted that the vessel WILL BE eligible for the next MBS 11/63 when the survey has been completed.

Subject

Subject as above re Item (2) and as above as now amended re Item (1). *SL*

To complete MBS -

P & C boilers to examine in their entirety
 SV > off all (3) boilers to be aligned under station
 Oil burning system and related controls to examine
 Sludge to re-examine and repairs to CC stops
 and air heater tubes