

(LLOYD'S REGISTER.)
VESSELS OF 100 TONS AND UPWARDS.

G.R. 130.
Lloyd's Register.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping.
 Signal Letters (if any) K.W.N.Q.

Official Number.	Name of Ship.	No., Date, and Port of Registry.
149,654.	Pacheco.	51-1927 Liverpool.

No., Date, and Port of Previous Registry (if any). **New ship.**

Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Motor Ship Single Screw.	Govan	1927	Harland & Wolff Ltd., Govan.

Number of Decks ...	Two	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ...	Feet.	Tenths.
Number of Masts ...	Two		270	1
Rigged ...	Schooner	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ...	270	0
Stern ...	Elliptical		39	1.5
Build ...	Clencher	Main breadth to outside of plating ...	15	6.0
Galleries ...	None		26	3.1
Head ...	None	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ...	25	7.1
Framework and description of vessel ...	Steel Cargo		40	2.5
Number of Bulkheads ...	Five	Depth from top of beam amidships to top of keel ...		
Number of water ballast tanks, and their capacity in tons ...	Ten 354 tons			
		Round of beam ...		
		Length of engine room, if any ...		

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ... } **3979** Tons. | Ditto per inch immersion at same depth ... } **20.53** Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. B. H. P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.		
One	Vertical Reciprocating Internal Combustion	British	1927	Harland & Wolff Ltd., Govan.	Six 630m/m 1300 m/m	4 Stroke Single Acting		350 1550 2060
One	Particulars of Boilers.	Boilers.	Boilers	Boilers.	115 Revs. per minute		12 1/4 knots	

PARTICULARS OF TONNAGE.

GROSS TONNAGE.		No. of Tons.	DEDUCTIONS ALLOWED.		No. of Tons.
Under Tonnage Deck ...		1054.93	On account of space required for propelling power		647.55
Space or spaces between Decks ...			On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew		
Turret or Trunk ...			These spaces are the following, viz.:-		
Forecastle ...		11.30	in		
Bridge space	Poop	25.01	Poop Round Houses and Side Houses.		117.59
Peep or Break ...		6.19	No. of Seamen or Apprentices for whom accommodation is certified - 33		
Side Houses ...		73.40			
Deck Houses ...		69.68			
Chart House ...		5.97			
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ...		99.27	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:-		
Excess of Hatchways ...			Master's Accommodation 11.64		
			Chart Space 5.97		50.79
			Wireless Space 4.15		
			Boatswain's Store Spaces 13.46		
			Water Ballast Spaces 15.57		
			Total ...		815.93
Gross Tonnage ...		1345.75	Cubic Metres		
Deductions, as per Contra ...		815.93	3808.47		
Register Tonnage ...		529.82	2309.08		
			1499.39		

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is **272.00** tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is **142.59** tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.					
Shelter 'Tween Decks Part I L.47.9-152.55 tons	Shelter 'Tween Decks, Part III L.115.0-372.52				
Deductions 1.31 "	Deductions 70.48				
151.24 "					
Shelter 'Tween Decks Part II L.65.15-207.04 "					302.04
Deductions 2.26 "	Tonnage Well L.5.75 "				17.87
204.78 "					
Passageways abreast Side House on Shelter Deck L.72.7, L.72.7 - 37.14 tons					

Name of Master **David Hamer** Certificate of { Service No. 006861
Competency No. 006861

No. of Owners
 Name, Residence, and Description of Managing Owner if there are more owners than one.

MacAndrews & Co., Limited,
 Goree, Water Street,
 Liverpool.
 Sixty-four Shares.

William Lewis of Goree,
 Water Street, Liverpool
 -Manager-

Dated **20th December, 1927.**

