

Total

Gross Tonnage

Register Tonnage

Depth, at middle of length from top of keel to top
of beam at side of uppermost continuous
deck. See Sec. 3 (1c)

1st Longitudinal Number (L x D)

2nd Numeral L x (B + D)

D 9.71

Owners Republik Indo

Managers

(Where necessary to be entered in Reg. Book)

3rd, 10.52

Schw. Waterhuizen, J. Pattje.

Yard No. 216.

Sister ship "BARLIAN"

M.M. 10286

Received by Chief Ship Surveyor

Received from Chief Ship Surveyor

SHIP'S NAME Sin.Sc. Motorship "BIDURI"

REPORT

Gro.

No. 842a

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

L. 171.6' B. 31.82' D. 9.71'.

The scantlings and arrangements, as reported, conform with the Society's Revised Rules and Regulations, and are in accordance with or equivalent to those shown on the approved plans.

It is therefore submitted the ship is eligible to be classed:-

100A1

1 Dk. "pt.elec.Welded".

Cell DB amidships 49' 38t; DBf 56' 80t; DT 14' 126t; FPT 38t; APTs pt W.B. 20t pt O.F.

FK, 6BH, Asp. Lloyd's A & CP.

P. 42' Q. 42' B. 80' RFD 55' F. 22'

Mchy aft

O.L. 192'

ESD

"j"

REVISED CERTIFICATE

C.S.S. Records Dept.

to note increased length
of cable.

It is further submitted the Surveyor be requested to

- 1) conform the depth of the W.T. bulkhead stiffeners at A.P. and No.49 bulkhead to be 115 mm. as given on the plans "As Built", and
- 2) explain why plans Nos. 72705 and 72709, which are enclosed, do not agree with plan No. 72703 especially with reference to the position of the fore peak bulkhead.

NOTE:- Plans Nos. 72705 and 72709 to be returned to the Groningen Surveyors. (also 72703)

13.8.53.


DOUBLE BOTTOM.

Solid Floors, thickness and spacing

" " Are Frame and Reversed Frame
joggled?

7 2200

40

Bridge Deck, Angle, 

Spacing

010283-010288-0111

Spacing

Foundation

75 75

550



© 2021

Lloyd's Register
Foundation