



ANCHORS
3 BOW ANCHORS STOCKLESS 65,000 LBS. (10' DIA.)
3 WITH REDUCTIONS AS PER RULE - 192 CWT'S TOTAL WEIGHT
1 STREAM ANCHOR EXCLUSIVE OF STOCK 17 1/2 CWT'S (10' DIA.)
1 KEDGE ANCHOR EXCLUSIVE OF STOCK 7 1/2 CWT'S (10' DIA.)

CHAIN CABLES, HAWSERS, ETC.
270 FATHOMS STUD LINK CHAIN 3/4" MIN. WT. 500 LBS. (10' DIA.)
30 FATHOMS STUD LINK CHAIN 1/2" MIN. WT. 100 LBS. (10' DIA.)
OR 30 FATHOMS 3/4" STEEL WIRE BREAKING STRENGTH 500 LBS.
HAWSERS AND WARPS 3 OF 6" AND 2 OF 3" 30 FATHOMS EACH
TOWLINE 120 FATHOMS 5" STEEL WIRE.

LLOYD'S NUMERALS
DIMENSIONS 401'-0" x 54'-0" x 32'-0" MID TO UPPER DECK
BEAM B 54'-0"
DEPTH D 32'-0"
B + D 86'-0" FIRST NUMBER following 40 is 86
LENGTH 401'-0" SECOND NUMBER following 40 is 01

LENGTH OF BRIDGE 123'-0"
LENGTH OF POOP 56'-0"
LENGTH OF FORECASTLE 44'-0"

2- With Tank Side Brackets = 20'-0"
increased as indicated

APPROVED
25-1-1921
BY ADJUTANT
OF THE COMMISSIONER
NAVY
1921

APPROVED
NAME
DATE
BY
DATE

Monfalcone L^o III - III

Approved sketch of Midship section

N^o III. - St. Lucia * Tri. Rep. 5362 — Dioclass Section 239
N^o 112 St. Teresa. Tri. Rep. 5470

010294 - 010291 - 0203



© 2021

Lloyd's Register
Foundation