

17 JUL 1944

Fed. 2159.

Index No.....

Lloyd's Register of Shipping.

Ship's Name

SANTINI REVALA

Official No. 168961.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in

The following modifications to the accommodation for the defence personnel within the after tween deck spaces have now been effected:-

P.S. 1 - 25" diameter steel escape scuttle of substantial construction, provided with jointed and hinged steel cover with locking device, fitted on weather deck abreast No. 5 hatch, in way of fore end of tween deck accommodation. Coaming height 20".

2 - 8" steel cowl type vents, coaming height 25", each provided with wood plug and canvas cover, fitted additionally at fore and after ends respectively of tween deck accommodation.

3 - 12" clear glass side scuttles, provided with hinged deadlights, fitted at fore end of tween deck accommodation, additional to those already provided.

S.S. 1 - 12" clear glass side scuttle fitted at fore end of tween deck accommodation, provided with hinged dead light.

1 - 8" steel cowl type vent, coaming height 25", provided with wood plug and canvas cover, fitted additionally in way of existing tween deck accommodation.



*M. A. L. -
17 JULY 1944
Hull
of Ship*