

18 JAN 1945

Rpt. C. 11 (Contd.)

Index No. ....

# Lloyd's Register of Shipping.

Ship's Name "TEKOA".

Official No. 145994.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Bilge and separator discharges (originally discharging into starboard ash shoot now led overboard through common pipes with storm valve at shell.

Sanitary overflow from casing top now led overboard.

*W. Robinson*

SURVEYOR TO LLOYD'S REGISTER.

*Liverpool 145.*

*Noted*  
18 JAN 1945  
*J.P.S.*

*Extract from Liverpool Report 122109. 10.1.45.*

*Condition:- Examined starboard ash shoot & found same heavily wasted & holed below water line. As this shoot is not now essential (oil burning vessel) the lower portion of shoot has been cropped & removed from stockhold & a doubling plate fitted over the shell opening*

*Noted*  
18 JAN 1945  
*J.P.S.*

010338-010354-0213

