

Port of Bremen

Continuation of Report No. -

dated -

on the

LLOYD'S REGISTER OF SHIPPING

SHIP'S NAME: "IDKERBERG"

OFFICIAL NUMBER: 9173

MEMORANDUM OF ALTERATIONS REPORTED SINCE SHIP WAS SURVEYED FOR ASSIGNMENT OF LOAD
LINES IN April 1955 at Bremen.

ALTERATIONS: -

New access hatches fitted on upper deck between Nos.1 & 2 and Nos.4 & 5 cargo
hatches within line of openings.

Between Nos.1 & 2 hatches


Port 610 mm diam. 8 mm coaming 610 mm high closed by hinged steel water-
tight cover secured by toggles.

Starboard 610 mm x 610 mm, 8 mm coaming, 610 mm high closed by hinged steel water-
tight cover secured by toggles.

Between Nos.4 & 5 hatches

Port 610 mm x 610 mm, 8 mm coaming 610 mm high closed by hinged steel
watertight cover secured by toggles.

Starboard 610 mm diam., 8 mm coaming, 610 mm high closed by hinged steel
watertight cover secured by toggles.



20 APR 1955

Copy to be sent
to owner for
placing on
board ship
28



© 2021

Lloyd's Register
Foundation